MINNESOTA DEPARTMENT OF TRANSPORTATION CITY OF LINO LAKES

REC'D 8-14-12 CAK

LEGEND


EXISTING CONDITIONS AND REMOVALS


	EXIST. RIGHT-OF-WAY
	EXIST, PROPERTY LINE
==== <u>B618_046</u> ==	EXIST, CONC. CURB AND GUTTER
CONC_CURB	EXIST. CURB (TYPE AS NOTED)
	EXIST, EDGE OF BIT, SURFACE
	EXIST, EDGE OF GRAVEL
CONC.WALK	EXIST. SIDEWALK (TYPE AS NOTED)
<i>p</i> / +	EXIST, POWER POLE, GUY
☆ □	EXIST. LIGHT POLE, HAND HOLE
※ 12" ◯ 12"	EXIST. TREE
x x	EXIST. CHAIN LINK FENCE
	EXIST. WOOD FENCE
(************************************	EXIST, RETAINING WALL
Concess of the Conces	EXIST. BUILDING
	EXIST, SANITARY SEWER
<	EXIST. STORM SEWER (12"-36")
==<====	EXIST. STORM SEWER (> 42")
Ö	EXIST. MANHOLE
B 0	EXIST. CATCHBASIN
W	EXIST. WATERMAIN
∳&∉	HYDRANT, GATE VALVE
G	EXIST, GAS MAIN
— ЕЕ	BURIED ELECTRIC
E2	ELECTRIC BOX
TT	BURIED TELEPHONE
22	TELEPHONE PEDESTAL
vT	BURIED CABLE TELEVISION

CONSTRUCTION PLAN FOR: SUBGRADE PREPARATION, AGGREGATE BASE, BIT MIL, BIT PAVING, STORM SEWER, TRAILS, AND APPURTENANT WORK

LOCATED ON: BIRCH STREET FROM APPROX. 450' FEET EAST OF HODGSON ROAD TO APPROX. 2000' FEET EAST. SIOUX LANE FROM 350' FEET EAST OF SIOUX LOOKOUT TO HOKAH DRIVE.

> S.A.P. 002-634-002, BIRCH ST (CSAH 34) 1550 FEET 0.29 MILES 0 FEET 0 MILES 0 FEET 0 MILES GROSS LENGTH BRIDGES-LENGTH EXCEPTIONS-LENGTH 1550 FEET 0.29 MILES







TREE GRATE SIGNAL POLE

> DESIGN DESIGNATION BIRCH STREET (CSAH 34) Present ADT (2012) = 13,300 No. of Traffic Lanes = 2 Projected ADT (2032) = 19,000 No. Of Parking Lanes = 0

Design Speed = 50 MPH
Soil Factor = 50%
Functional Classification = B MINOR ARTERIAL Stopping Sight Distance Based On: 3.5 Height Of Eyes And 2.0" Height Of Object





GOVERNING SPECIFICATIONS

- . THE 2005 EDITION OF THE MINNESOTA DEPARTMENT OF TRANSPORTATION "STANDARD SPECIFICATIONS FOR CONSTRUCTION" SHALL GOVERN.
- ALL TRAFFIC CONTROL DEVICES SHALL CONFORM AND BE INSTALLED IN ACCORDANCE TO THE "MINNESOTA MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES" (MN MUTCD) AND PART VI, "FIELD MANUAL FOR TEMPORARY TRAFFIC CONTROL ZONE

INDEX						
SHEET NO.	DESCRIPTION					
1	TITLE SHEET					
2	GENERAL LAYOUT					
3-4	ESTIMATED QUANTITIES					
5	STANDARD PLATES AND SOILS CONSTRUCTION NOTES					
6-9	TYPICAL SECTIONS					
10	MISCELLANEOUS DETAILS					
11-15	PEDESTRIAN CURB RAMP DETAILS					
16-20	STAGING AND TRAFFIC CONTROL					
21-22	AUGNMENT PLAN					
23-24	INPLACE TOPO, UTILITIES AND REMOVAL PLAN					
25-27	CONSTRUCTION PLAN AND PROFILE					
28-29	INTERSECTION DETAIL					
30-31	STORM WATER POLLUTION PREVENTION PLAN NOTES					
32	DRAINAGE PLAN AND TABULATION					
33	DRAINAGE PROFILE AND TABULATION					
34	EROSION CONTROL AND TURF ESTABLISHMENT					
35-37	EROSION CONTROL DETAILS					
38	POND GRADING AND EARTHWORK SUMMARY					
39	SIGNING AND STRIPING TABULATION					
40	SIGNING AND STRIPING PLAN					
41-45	SIGNING AND STRIPING DETAILS					
46-56	SIGNALS PLAN AND DETAIL					
57-63	CROSS SECTIONS					
	THIS PLAN CONTAINS 63 SHEETS					

I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED ENGINEER UNDER THE LAWS OF THE STATE OF PRINTED NAME: JAMES E. STUDENSKI




LIC. NO. 23757

INO LAKES ENGINEER

TATE AID APPROVALS:	
MAICO	/
	<u> </u>
METRO DISTRICT STATE AD ENGINEER: REVIEWED FO	R

APPROVED FOR STATE FUNDING STATE AID ENGINEER.

/12



				ESTIMATE	D QUANTITIE	ES			
SHEET NO.	ITEM NUMBER	ITEM	NOTE NO.	UNIT	TOTAL ESTIMATED QUANTITY	CITY OF LINO LAKES BIRCH STREET NON-PARTICIPATING	ANOKA COUNTY BIRCH STREET S.A.P. 002-634-002	CITY OF LINO LAKES WARE ROAD NON-PARTICIPATING	CITY OF LINO LAKES SIOUX LANE NON-PARTICIPATING
						QUANTITY	QUANTITY	QUANTITY	QUANTITY
	2021,501	MOBILIZATION		LUMP SUM	1	0.31	0.43	0.17	0.09
	0404.554						<u> </u>		***************************************
		CLEARING CLEARING	(6)	ACRE	0.35	0.35			· ····
		GRUBBING	(6) (6)	TREE	0.35	0.35	***************************************		
		GRUBBING	(6)	ACRE	1	0.33			
	2101.001			7,01,2	<u>'</u>		*****		******
	2104.501	REMOVE CONCRETE CURB AND GUTTER		LINFT	280		80	125	75
	2105.501	REMOVE BITUMINOUS CURB	-	LINFT	75		75	***************************************	***************************************
	2106.503	REMOVE BITUMINOUS DRIVEWAY PAVEMENT		SQ FT	2433		2185	248	*****
	***************************************	REMOVE BITUMINOUS PAVEMENT	(7)	SQ YĐ	2142		2092		50
	2105.505	REMOVE BITUMINOUS TRAIL	(7)	SQ YD	838		838		
	0404.000						***************************************		
,	2104.509	REMOVE SIGN TYPE C		EACH	7	7			
	2104 513	SAWING BIT PAVEMENT (FULL DEPTH)		LIN FT	5178	<u></u>	5078		100
×		SALVAGE MAIL BOX AND SUPPORT		EACH	7	7	JU/8	A	100
		SALVAGE & REINSTALL IRRIGATION SYSTEM		EACH	2	4	· · · · · · · · · · · · · · · · · · ·		2
		SALVAGE SIGN TYPE C		EACH	3	3			<u> </u>
		ABANDON STRUCTURE		EACH	1	1		· · · · · · · · · · · · · · · · · · ·	
	2105.501	COMMON EXCAVATION (P)	(4)	CU YD	1390	1133			257
	2105.511	COMMON CHANNEL EXCAVATION	(5)	CU YD	1121	1121			
		TORON DODDOWAYOU ILIA	/251						
		TOPSOIL BORROW MOD (LV) TOPSOIL BORROW (CV)	(15)	CUYD	115	115			
	····	DEWATERING		CU YD LUMP SUM	329	329		,	
	2103.601	DEGYATERING		LUMP SUM	1	1		***************************************	
	2211.503	AGGREGATE BASE (CV) CLASS 5 (P)		CU YD	732	***************************************	560		172
	***************************************	AGGREGATE SHOULDERING (CV) CLASS 2 MOD		CUYD	50	\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\	50		
	2232.501	MILL BITUMINOUS SURFACE (2.0")	character and a second	SQ YD	7646		7646		
				~					
		TYPE SP 12.5 WEARING COURSE MIX (4,E)	(8)	TON	1205	***************************************	1205		
		TYPE SP 12.5 WEARING COURSE MIX (2,8)	(8)	TON	67				67
······		TYPE SP 12.5 NON WEAR COURSE MIX (4,B)	(1)(8)	TON	580		580		
	2360.503	TYPE SP 12.5 NON WEAR COURSE MIX (2,B)	(1)(8)	TON	89	x	trondayoron and an analysis,	414	89
	2501.515	24" RC PIPE APRON		EACH	1		. 1		
		TRASH GUARD FOR 24" PIPE APRON		EACH	1		1		
	Archannhaman		***************************************			·····	1	····	· · · · · · · · · · · · · · · · · · ·
		4" PERF PE PIPE DRAIN	(2)	LIN FT	100	100			
	2502.602	4" PE PIPE DRAIN CLEANOUT	-	EACH	1	1			
		15" RC PIPE SEWER DES 3006 CL II		LINFT	660	300	300		60
		18" RC PIPE SEWER DES 3006 CL II 24" RC PIPE SEWER DES 3006 CL II		LINFT	414	207	207		
	2003.041	24 NOT THE DEWEN DES SOUS OF II		LIN FT	220	110	110		
	2504.602	ADJUST GATE VALVE		EACH	6	6			
		CONNECT TO EXISTING WATER MAIN		EACH	1	<u> </u>			1
	2504.602	HYDRANT		EACH	2				2
	**	6" GATE VALVE		EACH	2				2
	~~~~~	1" CORPORATION STOP		EACH	4	7,17,			4
		1" CURB STOP & BOX		EACH	4		***************************************		4
		1" TYPE K COPPER PIPE	<b></b>	LINFT	119				119
***************************************		6" WATERMAIN DUCTILE IRON CL 52		LINFT	13		44-4		13
	·	8" WATERMAIN DUCTILE IRON CL 52 2" POLYSTYRENE INSULATION	ļ	LIN FT SY	425 50			***************************************	425
	***************************************	DUCTILE IRON FITTINGS		LB	50 288			***************************************	50 288
l	2.004.000	DOCTE A COLL 12 STACO	L	LD LD	400	<b></b>	ļ	I	288

- 3" THICK WEAR COURSE MIX SHALL BE USED FOR DRIVEWAYS AND SHALL BE PLACED IN ONE LIFT.
- INCLUDES INSTALLATION OF 4" PERFORATED PE PIPE WITH A FILTER SOCK EMBEDDED IN ONE FOOT OF GRAVEL ON BOTH SIDES OF PIPE.
- POND OVERFLOW SEE SHEET NO. 45 FOR DETAILS.
- INCLUDES INPLACE TOPSOIL. TOPSOIL ENCOUNTERED IN THE PROJECT LIMITS IS ASSUMED TO BE 4" AND SHALL BE STOCKPILED FOR SLOPE DRESSING. ANY MATERIAL NOT USED ON PROJECT, OTHER THAN TOPSOIL, SHALL BECOME THE PROPERTY OF THE CONTRACTOR AND SHALL BE DISPOSED OUTSIDE THE PROJECT OF MAY
- NO ATTEMPT HAS BEEN MADE TO DETERMINE THE TYPE OF MATERIAL TO BE EXCAVATED.
- LIMITS OF CLEARING AND GRUBBING SHALL BE STAKED IN THE FIELD.
- SPEC. 2360 BITUMINOUS MIXTURES COMPUTED AT 113 POUNDS / SQ YD / INCH.
- ALL TRAFFIC CONTROL AND SIGNING SHALL CONFORM TO THE MMUTCD INCLUDING "FIELD MANUAL FOR TEMPORARY TRAFFIC CONTROL ZONE LAYOUTS".
- INCLUDES REMOVING SEDIMENT BUILD-UP AND REPAIRING, REPLACING, OR SUPPLEMENTING WHEN NON-FUNCTIONAL.
- LUMP SUM ITEM INCLUDES INSTALLATION, MAINTENANCE AND REMOVAL OF CULVERT END PROTECTION FOR THE LIFE OF THE PROJECT.
- FERTILIZER ANALYSIS 18-1-18, APPLIED AT A RATE OF 150 LBS PER ACRE (13)
- SEED MIX 350 APPLIED AT A RATE OF 84.5 POUNDS/ACRE.
- PLANTING MEDIUM FOR FILTRATION PONDS AND SWALES. A WELL BLENDED, HOMOGENOUS MIXTURE OF 55-65% CONSTRUCTION SAND; 10-20% TOP SOIL; AND 25-35% ORGANIC LEAF COMPOST.

			7			
				<u>[</u>		I HEREBY CERTIFY
						BY ME OR UNDER MY
	***************************************					I AM A DULY LICE UNDER THE LAWS
	-Chihara Amarana and an and an					UNDER THE LAWS
				1		1
						SIGNATURE: Barre
		+	<del> </del>			SIGNATURE: JAME PRINTED NAME: JAME
	THE PROPERTY OF THE PARTY OF TH		<u> </u>			
ΝO	DATE	BY	CKD	APPR	REVISION	DATE: 7/23/2012

PRINTED NAME: JAMES E. STUDENSKI

___ LIC. NO. 23757

S.A.P. 002-634-002 TKDA Proj. 14851.000 S.P. S.P.



### CITY OF LINO LAKES

SHEET ESTIMATED QUANTITIES BIRCH ST (CSAH 34)/WARE RD SIGNALIZATION

				ESTIMATE	D QUANTITIE	S			· · · · · · · · · · · · · · · · · · ·
SHEET NO.	ITEM NUMBER	ιτεм	NOTE NO.	UNIT	TOTAL ESTIMATED QUANTITY	CITY OF LINO LAKES BIRCH STREET NON- PARTICIPATING	ANOKA COUNTY BIRCH STREET S.A.P. 002-634-002	CITY OF LINO LAKES WARE ROAD NON-PARTICIPATING	CITY OF LINO LAKES SIOUX LANE NON-PARTICIPATING
						QUANTITY	QUANTITY	QUANTITY	QUANTITY
	2506,501	CONSTRUCT DRAINAGE STRUCTURE DESIGN H		LIN FT	19.3	19.3	· · · · · · · · · · · · · · · · · · ·		
	2506.501	CONSTRUCT DRAINAGE STRUCTURE DESIGN 402		LIN FT	8				8
	2506.501	CONSTRUCT DRAINAGE STRUCTURE DES 48-4020		LIN FT	21.7	17.2			4.5
albandera elalimino benderenda ra	2506.501	CONSTRUCT DRAINAGE STRUCTURE DES 60-4020		LIN FT	4.87	4.87	A	.,.,	
	2506.602	CONNECT INTO EXISTING DRAINAGE STRUCTURE		EACH	1				1
	2506.516	CASTING ASSEMBLY		EACH	9	9			···,·
		ADJUST FRAME & RING CASTING		EACH	5	5			······································
	2506.602	CONSTRUCT POND OVERFLOW	(3)	EACH	1	1			
	2511.501	RANDOM RIPRAP CLASS III		CU YD	30	30			
	0504 504	AL CONCOUNTY MALIA		00 57	5050				
		4" CONCRETE WALK 2" BITUMINOUS TRAIL		SQ FT SQ FT	5939 7059	5939	<b>ጎ</b> ስድር		
		6" CONCRETE DRIVEWAY PAVEMENT		SQ YD	7059	84	7059		
ļ	2531.501	CONCRETE CURB & GUTTER DESIGN 8418		LIN FT	3002	1501	1501		<del></del>
	2531.501	CONCRETE CURB & GUTTER DESIGN 8618		LINFT	100	50	50		
	2531.501	CONCRETE CURB & GUTTER DESIGN D412		LIN FT	470				470
	2531.618	TRUNCATED DOMES		SQ FT	96	96			
		* * * * * * * * * * * * * * * * * * * *							.,,,
		INSTALL MAILBOX & SUPPORT		EACH	7	7			
	2540,602	MAILBOX SUPPORT		EACH	7	7			A
	2554.509	GUIDE POST TYPE B		EACH	1		1		***************************************
		TRAFFIC CONTROL	(9)	LUMP SUM	1	0.31	0.43	0.17	0.09
	2564.531	SIGN PANELS TYPE C	(10)	SQ FT	60,5	60.5		***************************************	
	2564.537	INSTALL SIGN TYPE C	(10)	EACH	3	3	***************************************		
	2564.602	INSTALL DELINEATOR		EACH	4	4			
	2565.511	TRAFFIC CONTROL SIGNAL SYSTEM B		SIGS		0.25			
	~~~~~~~~	EMERGENCY VEHICLE PREEMPTION SYSTEM B		LS	1	0.25 1	0.25	0.5	
harry homestra brancosco	2565.601	TRAFFIC CONTROL INTERCONNECTION		LS	1	0.25	0.25	0.5	
3						V-24	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	0.5	***************************************
	2573.530	STORM DRAIN INLET PROTECTION		EACH	11	11			***************************************
	2573,540	FILTER LOG TYPE COMPOST LOG	(11)	LIN FT	2400	2400			
	2572.604	CULVERT END PROTECTION	(12)	13 19 4Th CY 14 4					·····
	2573,602	TEMPORARY ROCK CONSTRUCTION ENTRANCE	(12)	LUMP SUM EACH	1	1			
	2010,002	TEM OTHER TOOK OCHOINGO HON EIGHTONOL		EACH					
	2575.501	SEEDING		ACRE	0.85	0.85			
	2575.502	SEED MIXTURE 350	(14)	POUND	72	72			

		MULCH MATERIAL TYPE 3 DISC ANCHORING		TON	1.7	1.7		,	····
		FERTILIZER TYPE 4	(13)	ACRE POUND	0,85 128	0.85 128	***************************************		
	2010,002	1 to 13 1 lo-Factor () ? 1 (to "7		FOOND	128	120			
	2582,501	PAVT MSSG (RT ARROW) POLY PREFORM		EACH	11		11		
	2582.501	PAVT MSSG (LT ARROW) POLY PREFORM		EACH	6	Andrews and the second	6	***************************************	
	0500 500	AR COLUMN LINE WAR HER TO CANO.	***************************************	1 11 2				· · ·	
	2582.502	4" SOLID LINE WHITE-EPOXY 4" SOLID LINE YELLOW-EPOXY		LINFT	6390		6390	~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~	********************************
		4" SOLID LINE YELLOW-EPOXY 4" DOUBLE SOLID LINE YELLOW-EPOXY		LIN FT LIN FT	1080 3125		1080 3125		
		24" SOLID LINE WHITE-POLY PREFORM		LINFT	3120 125		31.25 125	-(eg kakeran aran aran aran aran aran aran aran
		24" SOLID LINE YELLOW-POLY PREFORM		LIN FT	380	***************************************	380	***************************************	
		CROSSWALK MARKINGS-POLY PREFORM		SQFT	756		756		

NOTES:

- (P) DENOTES PLAN QUANTITY.
- (1) 3" THICK WEAR COURSE MIX SHALL BE USED FOR DRIVEWAYS AND SHALL BE PLACED IN ONE LIFT.
- (2) INCLUDES INSTALLATION OF 4" PERFORATED PE PIPE WITH A FILTER SOCK EMBEDDED IN ONE FOOT OF GRAVEL ON BOTH SIDES OF PIPE.
- (3) POND OVERFLOW SEE SHEET NO. 45 FOR DETAILS.
- (4) INCLUDES INPLACE TOPSOIL. TOPSOIL ENCOUNTERED IN THE PROJECT LIMITS IS ASSUMED TO BE 4" AND SHALL BE STOCKPILED FOR SLOPE DRESSING. ANY MATERIAL NOT USED ON PROJECT, OTHER THAN TOPSOIL, SHALL BECOME THE PROPERTY OF THE CONTRACTOR AND SHALL BE DISPOSED OUTSIDE THE RIGHT-OF-WAY.
- NO ATTEMPT HAS BEEN MADE TO DETERMINE THE TYPE OF MATERIAL TO BE EXCAVATED.
- (6) UMITS OF CLEARING AND GRUBBING SHALL BE STAKED IN THE FIELD.
-) DEPTH MAY VARY
- (8) SPEC. 2360 BITUMINOUS MIXTURES COMPUTED AT 113 POUNDS / SQ YD / INCH.
- 9) ALL TRAFFIC CONTROL AND SIGNING SHALL CONFORM TO THE MMUTCD INCLUDING "FIELD MANUAL FOR TEMPORARY TRAFFIC CONTROL ZONE LAYOUTS".
- (10) F&I SIGN POST SHALL BE INCIDENTAL.
- 11) INCLUDES REMOVING SEDIMENT BUILD-UP AND REPAIRING, REPLACING, OR SUPPLEMENTING WHEN NON-FUNCTIONAL.
- LUMP SUM ITEM INCLUDES INSTALLATION, MAINTENANCE AND REMOVAL OF CULVERT END PROTECTION FOR THE LIFE OF THE PROJECT.
- (13) FERTILIZER ANALYSIS 18-1-18, APPLIED AT A RATE OF 150 LBS PER ACRE
- (14) SEED MIX 350 APPLIED AT A RATE OF 84.5 POUNDS/ACRE.
- PLANTING MEDIUM FOR FILTRATION PONDS AND SWALES. A WELL BLENDED, HOMOGENOUS MIXTURE OF 55-65% CONSTRUCTION SAND; 10-20% TOP SOIL; AND 25-35% ORGANIC LEAF COMPOST.

	***************************************			,		
	~~					
			l			
						1
			l			1
NO	DATE	BY	CKD	APPR	REVISION	ĺ

I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE MATE OF MINNESOTA. SIGNATURE: PRINTED NAME: JAMES E. STUDENSKI

LIC. NO. 23757

S.A.P. 002-634-002
TKDA Proj. 14851.000
S.P.
BECKED BY DATE S.P.



CITY OF LINO LAKES

ESTIMATED QUANTITIES
BIRCH ST (CSAH 34)/WARE RD SIGNALIZATION

THESE STANDARD PLATES AS APPROVED BY THE FHWA SHALL APPLY

	STANDARD PLATES
PLATE NO.	DESCRIPTION
3000L	REINFORCED CONCRETE PIPE (5 SHEETS)
3006G	GASKET JOINT FOR R.C. PIPE (2 SHEETS)
3007D	SHEAR REINFORCEMENT FOR PRECAST DRAINAGE STRUCTURES
3022C	PRECAST CONCRET SAFETY APRON (3 SHEETS)
3040F	CORRUGATED METAL PIPE CULVERT (STANDARD 2-2/3" X 1/2" CORRUGATION)
3100G	CONCRETE APRON FOR REINFORCED CONCRETE PIPE
3133C	RIPRAP AT RCP OUTLETS
3134C	RIPRAP AT CMP OUTLETS
3145F	CONCRETE PIPE TIES
	CORRUGATED STEEL PIPE COUPLING BAND (3 SHEETS)
02220	The state of the s
4011E	PRECAST CONCRETE BASE
4020J	MANHOLE OR CATCH BASIN (FOR USE WITH OR WITHOUT TRAFFIC LOADS) (2 SHEETS)
4101D	RING CASTING FOR MANHOLE OR CATCH BASIN
4108F	ADJUSTING RINGS FOR CATCH BASINS AND MANHOLES
4110F	COVER CASTING FOR MANHOLE
4125D	CATCH BASIN FRAME CASTING (FOR SQUARE GRATE) - CASTING NO. 806
4134A	CURB BOX CASTING FOR CATCH BASIN (FOR DESIGN B CURBS) - CASTING NO. 825
41548	CATCH BASIN GRATE CASTING - CASTING NO. 816
7035N	CONCRETE WALVA CHAN DETUDIA AT EACH ALGER
7035N 7038A	CONCRETE WALK & CURB RETURNS AT ENTRANCES
	DETECTABLE WARNING SURFACE TRUNCATED DOMES CONCRETE CURB AND GUTTER (DESIGN B AND DESIGN V)
7100H 7102J	CONCRETE CORD AND GOTTER (DESIGN B AND DESIGN V) CONCRETE CURB AND GUTTER (DESIGN D, S, B4, B5, AND D3) (2 SHEETS)
71023 7109C	MEDIAN NOSE AND ISLAND (UNDIVIDED TO DIVIDED ROADWAY)
7111J	INSTALLATION OF CAST BASIN CASTINGS (CONCRETE CURB AND GUTTER)
71111 7113A	CONCRETE APPROACH NOSE DETAIL
7113M	CONCRETE APPROACH NOSE DETAIL
80001	STANDARD BARRICADES
8110E	TRAFFIC SIGNAL BRACKETING (POLE MOUNTED)
8111E	TRAFFIC SIGNAL BRACKETING (PEDESTAL MOUNTED) (3 SHEETS)
8112G	PEDESTAL FOUNDATION (TRAFFIC CONTROL SIGNALS)
8114A	P.V.C. HAND HOLE / PULL BOX (NO VEHICLE LOAD) (2 SHEETS)
8119C	GROUND MOUNTED CABINET FOUNDATION
8120P	POLE FOUNDATION (PA85)
8121G	TRANSFORMER BASE & POLE BASE PLATE (PA85, PA90, & PA100) (2 SHEETS)
8122F	PEDESTAL & PEDESTAL BASE (FOR TRAFFIC CONTROL SIGNALS SUPPORT) (2 SHEETS)
8123G	POLE & MAST ARM - LUMINARIES & TRAFFIC LIGHT ASSEMBLY (FOR ALL POLE TYPES) (2 SHEETS)
8126J	POLE FOUNDATION (PA90 & PA100)
8132B	PREFORMED RIGID PVC CONDUIT LOOP DETECTOR (3 SHEETS)
8150C	INSTALLATION OF CULVERT MARKERS
9350A	MAILBOX SUPPORT
9102D	TURF ESTABLISHMENT AREAS (AT PIPE CULVERT ENDS)

REVISION

PRINTED NAME: JAMES E. STUDENSKI

LIC. NO. 23757

DATE: 7/23/2012

S.A.P. 002-634-002 TKDA Proj. 14851.000 S.P. S.P.




CITY OF LINO LAKES


STANDARD PLATES, SOILS AND CONSTRUCTION NOTES


SHEE. 5 0F BIRCH ST (CSAH 34)/WARE RD SIGNALIZATION


SOILS AND CONSTRUCTION NOTES

- 1. THE GRADING GRADE IS DEFINED AS THE BOTTOM OF THE CLASS 5 OR 6 AGGREGATE.
- 2. SUITABLE GRADING MATERIAL ON THIS PROJECT SHALL CONSIST OF ALL SOILS ENCOUNTERED EXCEPT TOPSOIL, SILT, DEBRIS, ORGANIC MATERIAL, AND OTHER UNSTABLE MATERIAL
- 3. STRIP SOD AND TOPSOIL FROM AREAS TO BE DISTURBED BY CONSTRUCTION AND, IF PRACTICAL, STOCKPILE FOR REPLACEMENT LATER AS SLOPE DRESSING. TOPSOIL SHALL NOT BE REMOVED
- 4. SLOPE DRESSING IS DEFINED AS THE TOPSOIL OR OTHER SOIL PLACED DURING CONSTRUCTION TO PROVIDE A MEDIUM FOR ESTABLISHING TURF. IN ALL AREAS OF CONSTRUCTION, PROVIDE FOR A MINIMUM 4" OF SLOPE DRESSING.
- 5. THE TOP OF BACKSLOPES AND THE TOE OF FILL SLOPES SHALL BE ROUNDED TO NATURALIZE THE CONSTRUCTION EVEN THOUGH THE CROSS SECTIONS DO NOT SHOW ANY SUCH ROUNDING.
- 6. THE BOTTOM OF ALL SUBCUTS SHALL BE SHAPED AND COMPACTED BY THE "QUALITY COMPACTION METHOD".
- 7. OBTAIN COMPACTION ON THE GRADING PORTION OF PERMANENT CONSTRUCTION IN ACCORDANCE WITH THE "SPECIFIED DENSITY METHOD" REQUIREMENTS.
- 8. TEST ROLLING WILL NOT BE REQUIRED.
- 9. ANY DEBRIS WHICH MAY BE ENCOUNTERED DURING GRADING SHALL BE DISPOSED OF BY THE CONTRACTOR OFF THE PROJECT RIGHT OF WAY IN A SUITABLE DISPOSAL AREA AS APPROVED BY
- 10. THE CONSTRUCTION LIMITS AS SHOWN IN THE PLANS REPRESENT THE POINT OF INTERSECTION BETWEEN THE PROPOSED CUT OR FILL SLOPE AND THE EXISTING GROUND LINE AS DEPICTED ON THE CROSS SECTIONS. THE CONSTRUCTION LIMITS DO NOT INCLUDE AREAS REQUIRED FOR SLOPE ROUNDING
- 11. THE CONTRACTOR SHALL NOT STORE EXCAVATED MATERIAL OUTSIDE THE PLANNED CONSTRUCTION LIMITS UNLESS APPROVED BY THE ENGINEER
- 12. EARTHWORK FINISHING AND TOPSOIL COVERING OPERATIONS SHALL BE CONDUCTED CONCURRENTLY WITH GRADING OPERATIONS SO FAR AS TO PERMIT COMPLETION OF THE EROSION CONTROL ITEMS AT THE EARLIEST PRACTICAL TIME. TOPSOIL COVERING SHALL BE COMPLETED AS SOON AS POSSIBLE AFTER THE GRADING SOILS HAVE BEEN FINISHED TO GRADE IN ANY SIGNIFICANT AREA
- 13. SEED ALL AREAS DISTURBED BY CONSTRUCTION AS SHOWN ON THE EROSION CONTROL PLANS. ALL AREAS OUTSIDE THE PLANNED CONSTRUCTION DISTURBED BY THE CONTRACTOR'S EQUIPMENT SHALL BE RESTORED, AS APPROVED BY THE ENGINEER, AT THE CONTRACTOR'S EXPENSE
- 14. PROVIDE FOR THE REMOVAL AND DISPOSAL, OUTSIDE THE RIGHT-OF-WAY, OF ANY INPLACE SURFACING OR OTHER STRUCTURES THAT WOULD INTERFERE WITH CONSTRUCTION. ALL SUCH MATERIALS SHALL BECOME THE PROPERTY OF THE CONTRACTOR AND SHALL EITHER BE RECYCLED TO THE EXTENT ALLOWED OR DISPOSED OF OFF THE RIGHT-OF-WAY.
- 15. THE CONTRACTOR SHALL COORDINATE THE SALVAGE OR REMOVAL OF ALL MISCELLANEOUS STRUCTURES, SUCH AS PRIVATE SIGNS, WITHIN THE PROJECT LIMITS WITH THE APPROPRIATE
- 16. FOR ALL PERMANENT AND TEMPORARY CONSTRUCTION, PROVIDE A FULL DEPTH SAWCUT WHERE PLACING NEW PAVEMENT ADJACENT TO INPLACE PAVEMENT TO ENSURE A UNIFORM JOINT. ALL LONGITUDINAL SAWCUTS SHALL BE PLACED AT THE INSIDE EDGE OF PROPOSED LANE LINES. ALL TRANSVERSE SAWCUTS SHALL BE PERPENDICULAR TO PROPOSED LANELINES. SAWCUT EDGES SHALL BE TACK-COATED PRIOR TO PAVING (INCIDENTAL).
- 17. WHERE CONNECTING NEW SURFACING ADJACENT TO ANY INPLACE PAVEMENTS TO BE WIDENED, CUT VERTICALLY TO THE BOTTOM OF THE INPLACE SURFACING OR TO THE BOTTOM OF THE NEW SURFACING DESIGN, WHICHEVER IS DEEPER, THEN AT A 1 (V): 1 (H) SLOPE TO THE BOTTOM OF THE RECOMMENDED SUBGRADE EXCAVATION.
- 18. IN LOCATIONS OF WIDENING, THE CONTRACTOR SHALL MATCH THE EXISTING SOILS AND LAYERS IN THE UPPER 4 FEET OF THE ROADWAYS TO THE GREATEST EXTENT POSSIBLE. GRANULAR BACKFILL SHALL NOT BE PERMITTED ADJACENT TO EXISTING NON-GRANULAR (FROST SUSCEPTIBLE) SOILS IN ORDER TO PREVENT AN ABRUPT SOILS DIFFERENTIAL. THE CONTRACTOR SHALL PROVIDE A 1:1 (V:H) TRANSVERSE TRANSITION BETWEEN THE CHANGES IN MATERIAL TO PREVENT AN ABRUPT SOILS DIFFERENTIAL WHERE WIDENING ADJACENT TO NON-GRANULAR (FROST SUSCEPTIBLE) EXISTING SOILS
- 19. AS A PRECAUTIONARY MEASURE, TRAFFIC LANES TO BE USED DURING CONSTRUCTION MUST BE DELINEATED TO KEEP VEHICLES A SAFE DISTANCE AWAY FROM THE ADJACENT EXCAVATION. THE DELINEATION SHOULD COINCIDE WITH POINTS ESTABLISHED BY PROJECTING A 1V:2H OR FLATTER SLOPE BETWEEN THE EDGE OF THE TRAFFIC SURFACE AND THE BOTTOM OF THE EXCAVATION.
- 20. OBTAIN COMPACTION ON 4 INCH OR GREATER AGGREGATE BASE LIFTS IN ACCORDANCE WITH THE "MODIFIED PENETRATION INDEX METHOD" REQUIREMENTS. THE TESTS SHALL BE PERFORMED IN ACCORDANCE WITH MNDOT SPEC, 2211,3C3. THIS WOULD INCLUDE ANY AREAS WHERE CRUSHED CONCRETE OR SALVAGED ASPHALT MAY BE USED FOR AGGREGATE BASE. FOR LIFTS OF LESS THAN 4 INCHES OBTAIN COMPACTION IN ACCORDANCE WITH QUALITY COMPACTION METHOD (MNDOT SPEC, 2211,3C2).
- 21. THE CONTRACTOR SHALL SHAPE AND RECOMPACT ANY AGGREGATE BASE THAT IS EXPOSED AFTER MILLING THE BITUMINOUS SHOULDER PAVEMENT. THIS WORK SHALL BE PERFORMED AHEAD OF THE SHOULDER PAVING OPERATION AND BE DONE TO THE SATISFACTION OF THE ENGINEER. THIS WORK SHALL BE INCIDENTAL.
- 22. AFTER MILLING THE PAVEMENT TO THE REQUIRED DEPTH AND PRIOR TO OVERLAYING, AIR BLAST ANY DETERIORATED CRACKS AND JOINTS TO REMOVE LOOSE OR DETERIORATED BITUMINOUS SURFACING. THE AIR BLASTING SHALL BE DONE WITH HIGH-PRESSURE (100+ PSI) EQUIPMENT.
- 23. DEPRESSIONS RESULTING AFTER AIR BLASTING, SWEEPING OR MILLING OPERATIONS WHICH ARE GREATER THAN 2 INCHES IN DEPTH AND 4 INCHES IN WIDTH AND JOINTS AND CRACKS THAT ARE GREATER THAN 1-1/2 INCHES IN DEPTH AND WIDTH SHALL BE PATCHED WITH BITUMINOUS PATCHING MIXTURE. PATCHING OF THESE AREAS SHALL BE DONE AHEAD OF THE PAVING OPERATIONS AND COMPACTED WITH A SMALL VIBRATORY OR PNEUMATIC ROLLER. DEPRESSIONS OF LESSER DIMENSIONS SHALL BE FILLED WITH THE WEAR COURSE MIXTURE IN FRONT OF
- 24. ADDITIONAL WORK REQUIRED TO MILL AND OVERLAY AROUND MANHOLES AND VALVES, INCLUDING THOSE NOT SHOWN ON THE PLANS, SHALL BE INCIDENTAL.
- 25. TEMPORARY GRADING AND SURFACING MATERIALS REQUIRED TO FILL IN EXCAVATIONS TO MEET TEMPORARY DROP-OFF GUIDELINES AND MAINTAIN TEMPORARY PEDESTRIAN ACCESS ROUTES
- 26. PROVIDE FOR A UNIFORM BITUMINOUS TACK COAT BETWEEN ALL COURSES. PLACE BITUMINOUS MATERIAL FOR TACK COAT IN ACCORDANCE WITH SPECIFICATION 2357 AT A RATE OF 0.04 GALLONS PER SQUARE YARD BETWEEN BITUMINOUS LAYERS (INCIDENTAL),
- 27. BITUMINOUS PAVEMENT SHALL BE CONSTRUCTED IN LAYERS OF THE THICKNESS SPECIFIED IN THE CONSTRUCTION DETAILS AND TYPICAL SECTIONS. BITUMINOUS DRIVEWAYS SHALL BE CONSTRUCTED IN ONE 3" LAYER.
- 28. LOCATIONS OF UNDERGROUND UTILITIES SHOWN IN THE PLANS ARE APPROXIMATE LOCATIONS PROVIDED BY THE UTILITY OWNER, THE CONTRACTOR IS RESPONSIBLE FOR VERIFYING UTILITY LOCATIONS PRIOR TO ANY EXCAVATING OPERATIONS.
- 29. THE CONTRACTOR IS HEREBY REMINDED OF HIS RESPONSIBILITY UNDER STATE LAW TO CONTACT ALL UTILITIES THAT MAY HAVE FACILITIES IN THE AREA. CONTACT MUST BE MADE THROUGH GOPHER STATE ONE-CALL AND RAILROAD ENGINEERING REPRESENTATIVES.
- 30. PIPE SEWERS CONNECTING MANHOLES AND CATCHBASINS SHALL BE IN ACCORDANCE WITH SPEC. 2503. BEDDING AND BACKFILL SHALL CONSIST OF UNIFORM SUITABLE GRADING MATERIAL MATCHING ADJACENT SOILS LINLESS OTHERWISE DIRECTED BY THE ENGINEER
- 31. THE CONTRACTOR SHALL PRESERVE ALL LAND AND PROPERTY CORNERS, VERTICAL AND HORIZONTAL CONTROLS AND RIGHT OF WAY MONUMENTS
- 32. ALL CONCRETE TRUCKS SHALL WASH OUT WITHIN THE PROJECT LIMITS AWAY FROM ANY OPEN WATERS, DITCHES, OR WETLANDS AT A LOCATION SPECIFIED BY THE ENGINEER. HARDENED CONCRETE WASTE MUST BE REMOVED FROM THE PROJECT LIMITS AND PROPERLY DISPOSED. SEE SWPPP NOTES FOR ADDITIONAL POLLUTION PREVENTION MEASURES.










TYPICAL SECTION

WARE ROAD



NOTES:

- 1 MATCH INPLACE CROSS SLOPE.
- 2 SAWCUT 1' FROM EXISTING EDGE OF PAVEMENT OR LIP OF CURB AND REMOVE BITUMINOUS PAVEMENT. DEPTH VARIES.

TYPICAL SECTION

SIOUX LANE

NO DATE BY CKD APPR REVISION

I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROSESSIONAL ENGINEER UNDER THE LAWS OF THE TATE OF MINNESOTA.

SIGNATURE: PRINTED NAME: JAMES E. STUDENSK1

DATE: 7/23/2012 LIC. NO. 23757

DRAWN BY DATE S.A.P. 002-634-002
TKDA Proj. 14851.000
S.P.
CHECKED BY DATE S.P.

ATKIDA


ENGINEERING * ARCHITECTURE * PLANNING


CITY OF LINO LAKES

SHEET


TYPICAL SECTIONS
SIOUX LANE & WARE ROAD
BIRCH ST (CSAH 34)/WARE RD SIGNALIZATION

63







D412 CONCRETE CURB



B418 CONCRETE CURB & GUTTER




B618 CONCRETE CURB AND GUTTER



IMPERVIOUS SOILS.)

WIDTH (MAX 24') MATCH TO EXISTING SAW CUT EDGE (1/2" EXP. JOINT IF CONCRETE) 1/2" EXP. JOINT-IF CONCRETE CONTRACTION JOINT IF BITUMINOUS OR CONCRETE (PAVEMENT TYPE TO REPLACE EXISTING) CONCRETE
(PANEL WIDTH
NOT TO
EXCEED 10') TRANSITION -CURB FLOW LINE 1/2" EXP. JOINT A (TYP.) CONC. CURB-/ & GUTTER CURB & VARIABLE



SECTION A-A

DRIVEWAY TYPE	SURFACE THICKNESS	BASE_THICKNESS
BITUMINOUS	3 INCHES	6 INCHES
CONCRETE	6 INCHES	4 INCHES

NOTES

BITUMINOUS SHALL BE TYPE SP 12.5 WEAR COURSE SPEC 2360 (SPWEB440E).
 AGGREGATE BASE SHALL BE MnDOT 3136 CL. 5, 100% CRUSHED STONE.

8" CONCRETE 6" AGGREGATE BASE, CL. 5 TO BE PAID FOR AS CONCRETE DRIVEWAY PAVEMENT SECTION A-A

VARIABLE

WIDTH

*CROSSWALL

(SEE PLAN)

- 1/2" EXP. JOINT

FLOW. LINE

1/4" PER FOOT

EXIST. SIDEWALK

CONC. CURB-& GUTTER

CROSSWALK

CONTRACTION

JOINT

PANEL WIDTH SHALL NOT EXCEED 10' WITHOUT CONTR. JOINT.
 WHERE SIDEWALK EXISTS OR IS PROPOSED, CROSSWALK SHALL BE SAME THICKNESS AS DRIVEWAY.

COMMERCIAL CONCRETE DRIVEWAY

- 1/2" EXP. JOINT (TYP.)


EXIST.

SIDEWALK

RAD. (SEE PLAN)

BIT. SURF.-


RESIDENTIAL DRIVEWAY



① APPLY BITUMINOUS TACK COAT, MnDOT SPEC. 2357.

② SAW BITUMINOUS PAVEMENT FULL DEPTH TO ESTABLISH A NEAT LINE FROM WHICH TO EXTEND THE NEW WORK.

MILLED LAP JOINT DETAIL



A URETHANE OR BUTYL SEAL SHALL BE USED TO SEAL THE TOP RING TO THE CASTING AND THE BOTTOM RING TO THE CONE OR TOP SLAB. NO WOOD SHALL BE USED FOR ADJUSTING CASTING; CEMENT MORTAR ONLY. CAST IRON CATCH BASIN FRAME & COVER CASTINGS PER SPECIFICATIONS. PRECAST REINFORCED CONCRETE CONE SECTION & PRECAST BASE PER ASTM C478. FILL OPENING BETWEEN PIPE AND MANHOLE WALL WITH CEMENT MORTAR

BIRCH

* MINIMUM PIPE COVER CAN BE REDUCED FROM 4' TO 2'-6" WITH INSTALLATION OF PERFORATED PIPE DRAIN PER "GRANULAR SUBCUT AND PERFORATED PIPE DRAIN" DETAIL.

CATCH BASIN, TYPE 402


INSIDE SURFACE SHALL BE FINISHED SMOOTH.

		·			
		<u> </u>			
					_

NO	DATE	RY	CKD	APPR	REVISION
	NO				

TYPICAL HYDRANT LAYOUT


(VALVE IN BOULEVARD)




***************************************		S.A.P. 002-634-002 TKDA Proj. 14851.000
	DATE	S.P. S.P.




CITY OF LINO LAKES	SHEET
MISCELLANEOUS DETAILS	10
ST (CSAH 34)/WARE RD SIGNALIZATION	63







MAX. 2.0% LANDING 4'X4' MINIMUM ≤ 8.3% OPTIONAL V CURB-OR GRADING (8) 7 ≤ 2.0% MAX. 2.0% LANDING ≤ 2.0% 6 ≤8.3% 4'X4' MINIMUM **2**)-



DEPRESSED CORNER

PARALLEL





DIAGONAL @

FAN

NOTES:

SEE STANDARD PLATE 7038, AND SHEET 4 OF 5 FOR DETAILS ON DETECTABLE WARNING. SLOPES ARE DEFINED AS ABSOLUTE ELEVATION DIFFERENCE PER LENGTH OF RUN. (AS OPPOSED TO A RELATIVE SLOPE WITH RESPECT TO A CURB LINE OR CURB HEIGHT.) LANDINGS SHALL BE LOCATED ANYWHERE THE PEDESTRIAN ACCESS ROUTE CHANGES DIRECTION, AND AT THE TOP OF RAMPS THAT HAVE RUNNING SLOPES GREATER THAN 5%. INITIAL CURB RAMP LANDINGS SHALL BE CONSTRUCTED WITHIN 15' FROM THE BACK OF CURB WITH 6' FROM THE BACK OF CURB BEING THE PREFERRED DISTANCE, SECONDARY CURB RAMP LANDINGS ARE REQUIRED EVERY 30" OF VERTICAL RISE

WHEN THE LONGITUDINAL SLOPE IS 5% OR GREATER. CONTRACTION JOINTS SHALL BE CONSTRUCTED AT ALL GRADE BREAKS.

TOP OF CURB SHALL MATCH PROPOSED ADJACENT WALK GRADE.


USE 6" CONCRETE FOR ALL RAMP AND LANDING AREAS.

CONTRACTOR SHALL EMPLOY APPROPRIATE METHODS FOR INTERMEDIATE GRADE CONTROL TO ENSURE ALL GRADE BREAKS ARE CONSTRUCTED PROPERLY.

ALL GRADE BREAKS SHALL BE PERPENDICULAR TO THE DIRECTION OF TRAVEL/PEDESTRIAN ACCESS ROUTE.

- 1 O" CURB HEIGHT.
- ② FULL CURB HEIGHT.
- 3 LESS THAN 5% PREFERRED. 5-8.3% SHOULD ONLY BE USED AFTER ALL OTHER SLOPES HAVE BEEN CONSIDERED AND DEEMED IMPRACTICAL.
- (4) 1/2" PREFORMED JOINT FILLER MATERIAL AASHTO M 213. JOINT FILLER SHALL BE PLACED FLUSH WITH THE BACK OF CURB AND ADJACENT SIDEWALK, JOINT SHALL BE FREE OF DEBRIS. DOMES SHALL BE SET BACK 3" FROM THE BACK OF CURB OR EDGE OF ROADWAY.
- (5) SEE PEDESTRIAN ACCESS ROUTE CURB AND GUTTER DETAIL FOR INFORMATION ON CONSTRUCTING CURB AND GUTTER AT CURB OPENINGS. SEE SHEET NO. 3 OF 5.
- 6 4' BY 4' MIN. LANDING WITH MAX. 2% SLOPE IN ALL DIRECTIONS.
- T IF RUNNING SLOPE IS LESS THAN 5.0% NO UPPER LANDING IS REQUIRED.
- V CURB, IF USED, SHALL BE PLACED OUTSIDE THE SIDEWALK LIMITS WHEN ROW ALLOWS. SEE SHEET 5 OF 5.
- (9) DETECTABLE WARNINGS MAY BE PART OF 4' X 4' LANDING AREA IF IT IS NOT FEASIBLE TO CONSTRUCT THE LANDING OUTSIDE OF THE DETECTABLE WARNING AREA.
- (i) SEE SHEET 4 OF 5. TYPICAL SIDE TREATMENT OPTIONS, FOR DETAILS ON FLARES AND RETURNED CURBS.
- (1) ANY VERTICAL LIP THAT OCCURS AT THE FLOW LINE MAY NOT BE GREATER THAN 1/4 INCH. SEE INSET A ON SHEET 3 OF 5 FOR FURTHER DETAIL.
- (2) DIAGONAL RAMPS SHOULD ONLY BE USED AFTER ALL OTHER CURB RAMP TYPES HAVE BEEN CONSIDERED AND DEEMED IMPRACTICAL.

TIERED PERPENDICULAR



CURB OR CURB AND GUTTER 4' 0" MIN.
REQUIRED LANDING -1/4" R. _CONCRETE - 0.02 FT./FT. MAX.(6)


SECTION A-A PERPENDICULAR/TIERED/DIAGONAL/FAN


SECTION B-B PARALLEL/DEPRESSED CORNER

TANDARD PLAN SHEET NO. 5-297.250 (1 OF 5) MAY 10, 2012

PEDESTRIAN CURB RAMP DETAILS

SHEET NO. 11 OF 63 SHEETS STATE AID PROJ. NO. 002-634-002 BIRCH STREET (CSAH 34)







ADJACENT TO NON-WALKABLE SURFACE


ADJACENT TO WALKABLE SURFACE

COMBINED DIRECTIONAL



ONE-WAY DIRECTIONAL





CURB FOR DIRECTIONAL RAMPS 12

NOTES:

SEE STANDARD PLATE 7038, AND SHEET 4 OF 5 FOR DETAILS ON DETECTABLE WARNING. SLOPES ARE DEFINED AS ABSOLUTE ELEVATION DIFFERENCE PER LENGTH OF RUN. (AS OPPOSED TO A RELATIVE SLOPE WITH RESPECT TO A CURB LINE OR CURB HEIGHT.) LANDINGS SHALL BE LOCATED ANYWHERE THE PEDESTRIAN ACCESS ROUTE CHANGES DIRECTION, AND AT THE TOP OF RAMPS THAT HAVE RUNNING SLOPES GREATER THAN 5%. INITIAL CURB RAMP LANDINGS SHALL BE CONSTRUCTED WITHIN 15' FROM THE BACK OF CURB WITH 6' FROM THE BACK OF CURB BEING THE PREFERRED DISTANCE. SECONDARY CURB RAMP LANDINGS ARE REQUIRED EVERY 30" OF VERTICAL RISE WHEN THE LONGITUDINAL SLOPE IS 5% OR GREATER.

CONTRACTION JOINTS SHALL BE CONSTRUCTED AT ALL GRADE BREAKS.

TOP OF CURB SHALL MATCH PROPOSED ADJACENT WALK GRADE.

USE 6" CONCRETE WALK FOR ALL RAMP AND LANDING AREAS.

CONTRACTOR SHALL EMPLOY APPROPRIATE METHODS FOR INTERMEDIATE GRADE CONTROL TO ENSURE ALL GRADE BREAKS ARE CONSTRUCTED PROPERLY.


ALL GRADE BREAKS SHALL BE PERPENDICULAR TO THE DIRECTION OF TRAVEL/PEDESTRIAN ACCESS ROUTE.


- 1 O" CURB HEIGHT.
- 2 FULL CURB HEIGHT.
- 3 3" MINIMUM CURB HEIGHT.
- 4 1/2" PREFORMED JOINT FILLER MATERIAL AASHTO M 213. JOINT FILLER SHALL BE PLACED FLUSH WITH THE BACK OF CURB AND ADJACENT SIDEWALK. JOINT SHALL BE FREE OF DEBRIS. DOMES SHALL BE SET BACK 3" FROM THE BACK OF CURB OR EDGE OF ROADWAY.
- (5) SEE PEDESTRIAN ACCESS ROUTE CURB AND GUTTER DETAIL FOR INFORMATION ON CONSTRUCTING CURB AND GUTTER AT CURB OPENINGS. SEE SHEET NO. 3 OF 5.
- 6 4' BY 4' MIN. LANDING WITH MAX. 2% SLOPE IN ALL DIRECTIONS.
- (7) IF RAMP SLOPE IS LESS THAN 5% NO UPPER LANDING IS REQUIRED.
- 8 V CURB, IF USED, SHALL BE PLACED OUTSIDE THE SIDEWALK LIMITS WHEN ROW ALLOWS.
- (9) RUNNING SLOPE LESS THAN OR EQUAL TO 8.3% & CROSS SLOPE LESS THAN OR
- \bigodot SEE SHEET 4 OF 5, TYPICAL SIDE TREATMENT OPTIONS, FOR DETAILS ON FLARES AND RETURNED CURBS.
- (1) MAX. 2% SLOPE IN ALL DIRECTIONS IN FRONT OF GRADE BREAK AND DRAIN TO FLOW LINE. SHALL BE CONSTRUCTED INTEGRAL WITH CURB AND GUTTER (SEE DIRECTIONAL CURB DETAIL ON THIS SHEET).
- (12) TO BE USED FOR ALL DIRECTIONAL RAMPS.
- (3) DOMES PLACED AT THE BACK OF CURB WHEN ALLOWABLE SETBACK CRITERIA IS EXCEEDED.

5-297.250 (2 OF 5)


PEDESTRIAN CURB RAMP DETAILS

SHEET NO. 12 OF 63 SHEETS STATE AID PROJ. NO. 002-634-002 BIRCH STREET (CSAH 34)







PAVED FLARES



PAVED FLARES




RETURNED CURB




GRADED FLARES


TYPICAL SIDE TREATMENT OPTIONS (5)



TYPICAL SIDEWALK SECTION AT QUADRANT




DETECTABLE WARNING SETBACK CRITERIA



RADIAL DETECTABLE WARNING AT RADIUS

DETECTABLE WARNING PLACEMENT



APPROACH NOSE DETAIL FOR DOWNSTREAM SIDE OF TRAFFIC

NOTES:

SEE STANDARD PLATE 7038, AND THIS SHEET FOR DETAILS ON DETECTABLE WARNING.

USE 6" CONCRETE WALK UP TO EXISTING SIDEWALK GRADES FOR ALL RAMP AND LANDING AREAS.

WHETHER A SURFACE IS WALKABLE OR NOT SHALL BE DETERMINED BY THE ENGINEER.


FLARE LENGTHS SHOULD BE LESS THAN 8' LONG MEASURED ALONG THE RAMPS FROM THE BACK OF CURB.

- (1) O" CURB HEIGHT.
- (2) FULL CURB HEIGHT.
- 3 SHALL BE 1:10 WHEN ADJACENT TO WALKABLE SURFACES, A PAVED FLARE SHOULD BE 2' WHEN ADJACENT TO NON-WALKABLE SURFACES WHILE A GRADED FLARE SHOULD BE 1:6.
- 4 IMMOVABLE OBJECT OR OBSTRUCTION.
- (5) SIDE TREATMENTS ARE APPLICABLE TO ALL RAMP TYPES AND SHOULD BE IMPLEMENTED AS NEEDED ON ALL RAMPS AS FIELD CONDITIONS DICTATE. THE ENGINEER SHALL DETERMINE THE RAMP SIDE TREATMENTS BASED ON MAINTENANCE OF BOTH ROADWAY AND SIDEWALK, ADJACENT PROPERTY CONSIDERATIONS, AND MITIGATING CONSTRUCTION IMPACTS.
- 6 DETECTABLE WARNING SHALL HAVE ONE CORNER 3" FROM THE BACK OF CURB.
- 7) SHALL BE 2' MAXIMUM OFFSET WHEN ADJACENT TO WALKABLE SURFACE AND 5' MAXIMUM OFFSET WHEN ADJACENT TO NON-WALKABLE SURFACE.
- (8) WHEN NO FLARES ARE PROPOSED, THE CONCRETE WALK SHALL BE FORMED AND CONSTRUCTED PERPENDICULAR TO THE BACK OF CURB. MAINTAIN 3" BETWEEN EDGE OF DOMES AND EDGE OF CONCRETE.
- (9) DETECTABLE WARNING TO BE PLACED AT AN UNIFORM OFFSET DISTANCE FROM 3" TO 6" FROM THE BACK OF CURB. IF NO CURB AND GUTTER IS PLACED IN RURAL SECTIONS, DETECTABLE WARNING SHALL BE PLACED 1' FROM THE EDGE OF ROADWAY TO PROVIDE CONCESTE ROADER.


STANDARD PLAN SHEET NO. 5-297,250 (4 OF 5) STANDARD APPROVED:

PEDESTRIAN CURB RAMP DETAILS


STATE AID PROJ. NO. 002-634-002 BIRCH STREET (CSAH 34) SHEET NO. 14 OF 63 SHEETS




CONCRETE WALK EDGES ADJACENT TO CONCRETE STRUCTURES




RAILROAD CROSSING PLAN VIEW




V CURB ADJACENT TO LANDSCAPE CURB WITHIN SIDEWALK LIMITS




V CURB ADJACENT TO LANDSCAPE CURB OUTSIDE SIDEWALK LIMTS






DETECTABLE EDGE AT QUADRANT (5)



V CURB AT CORNER



NOTES:

ALL V-CURB CONTRACTION JOINTS SHALL MATCH CONCRETE WALK JOINTS. V CURB SHALL BE PLACED OUTSIDE THE SIDEWALK LIMITS WHEN ROW ALLOWS.

V-CURB NEXT TO BUILDING SHALL BE A 4" WIDTH AND SHALL MATCH PREVIOUS TOP OF SIDEWALK ELEVATIONS.

- (1) END TAPERS AT TRANSITION SECTION SHALL MATCH INPLACE SIDEWALK GRADES.
- 2 ALL V-CURB SHALL MATCH BOTTOM OF ADJACENT WALK.
- 3 EDGE BETWEEN NEW V-CURB AND INPLACE STRUCTURE SHALL BE SEALED AND BOND BREAKER SHALL BE USED BETWEEN EXISTING STRUCTURE AND PLACED V-CURB.
- (4) EDGE OF DETECTABLE WARNING SURFACES SHALL BE PLACED 6' MINIMUM TO 15' MAXIMUM FROM THE CENTERLINE OF THE NEAREST RAIL. WHEN PEDESTRIAN GATES ARE PROVIDED, DETECTABLE WARNING SURFACES SHALL BE PLACED ON THE SIDE OF THE GATES OPPOSITE THE RAIL.

STANDARD PLAN SHEET NO. 5-297.250 (5 OF 5) TANDARD APPROVED MAY 10, 2012

PEDESTRIAN CURB RAMP DETAILS

GENERAL NOTES:

- ALL TRAFFIC CONTROL DEVICES SHALL CONFORM AND BE INSTALLED IN ACCORDANCE WITH THE "MINNESOTA MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES" (MNMUTCD) AND "FIELD MANUAL FOR TEMPORARY TRAFFIC CONTROL ZONE LAYOUTS".
- 2. FIELD CONDITIONS MAY REQUIRE MODIFICATIONS OF LAYOUTS AS DEEMED NECESSARY BY THE ENGINEER.
- 3. ALL DISTANCES ARE APPROXIMATE.
- 4. BARRICADES ARE 8 FOOT TYPE III AND SHALL BE REFLECTORIZED ON BOTH SIDES.
- OBLITERATING ANY CONFLICTING PAVEMENT MARKINGS SHALL BE INCIDENTAL.
- ALL TRAFFIC CONTROL DEVICES ON ROADS OPEN TO TRAFFIC THAT ARE NOT CONSISTENT WITH TRAFFIC OPERATIONS SHALL BE COVERED, REMOVED, OR REVISED (INCIDENTAL).
- 7. THE CONTRACTOR IS RESPONSIBLE FOR EXTRA SIGNING NEEDED TO FACILITATE TRAFFIC SWITCHES OR FOR TRANSITIONING TRAFFIC FROM ONE STAGE TO ANOTHER.
- 8. THE CONTRACTOR IS RESPONSIBLE FOR PROTECTING ANY WORK AREAS NEAR TRAFFIC IN ACCORDANCE WITH THE MNMUTCD INCLUDING THE "FIELD MANUAL FOR TEMPORARY TRAFFIC CONTROL ZONE LAYOUTS".
- 9. THE CONTRACTOR SHALL COORDINATE THE PERMANENT SIGNING SO THAT THE INSTALLATION OF THE PERMANENT SIGNS IS COMPLETED BEFORE THE ROADWAYS ARE OPEN TO TRAFFIC.
- 10.IF THE CONTRACTOR DESIRES TO PERFORM WORK IN A SEQUENCE OTHER THAN SHOWN IN THE PLANS, THE CONTRACTOR SHALL SUBMIT THE PROPOSED CHANGES, IN WRITING, TO THE ENGINEER FOR APPROVAL AT LEAST 10 WORKING DAYS PRIOR TO THE COMMENCEMENT OF THE WORK. IF THE SEQUENCE OF CONSTRUCTION CHANGES ARE APPROVED AND THE CHANGES RESULT IN CHANGES TO THE TRAFFIC CONTROL, THE CONTRACTOR SHALL SUBMIT, IN WRITING, REVISED TRAFFIC CONTROL PLANS TO THE ENGINEER FOR APPROVAL AT LEAST 14 DAYS PRIOR TO IMPLEMENTING THE TRAFFIC CONTROL.
- 11.SEE SIGNING DETAIL SHEETS FOR TYPICAL ERECTION DETAILS (FOR SIGNS TYPES "C & D").
- 12.ALL DRUMS, BARRICADES, AND SIGNS SHALL BE RETRO-REFLECTIVE.
- 13.THE DEVICES IN THIS TRAFFIC CONTROL PLAN SHALL BE FURNISHED, INSTALLED AND MAINTAINED UNLESS OTHERWISE NOTED.
- 14.ALL TRAFFIC CONTROL ITEMS SHALL BE INCLUDED IN THE LUMP SUM BID FOR TRAFFIC CONTROL.

SIGNING:

- 1. WHEN SIGNS ARE INSTALLED, THEY SHALL BE MOUNTED AT THE PROPER HEIGHT AND LATERAL OFFSET AS DETAILED IN THE MNMUTCD.
- 2. ALL ORANGE SIGNS SHALL BE MADE OF HIGH PERFORMANCE FLUORESENT SIGN SHEETING OR AN APPROVED SUBSTITUTE.
- 3. LONGITUDINAL DROP OFFS SHALL BE SIGNED AS SHOWN ON PAGES 6K-100 THROUGH 6K-102 OF THE "FIELD MANUAL FOR TEMPORARY TRAFFIC CONTROL ZONE LAYOUTS" UNLESS OTHERWISE SPECIFIED IN THESE PLANS.
- 4. REMOVAL OF EXISTING SIGNS SHALL BE COORDINATED WITH THE SIGNING PLANS. ANY CONFLICTING SIGNS SHALL BE REMOVED.
- THE REMOVAL OF THE TEMPORARY SIGNS WILL BE COORDINATED TO ASSURE THAT THE FINAL SIGNS ARE INSTALLED AS NEEDED, OR TEMPORARY SIGNING WILL BE PROVIDED UNTIL THE FINAL SIGNING IS INSTALLED.
- 6. EXISTING SIGNS MAY BE RE-USED FOR CONSTRUCTION SIGNING.

STAGING NARRATIVE

STAGE 1 (SEE SHEET 17)

CONSTRUCT POND AND STORM SEWER ALONG BIRCH ST. (CSAH 34) AND ALL CROSSINGS.

STAGE 2 (SEE SHEET 18)

SHIFT TRAFFIC TO SOUTH BIRCH STREET (CSAH 34) AND CONSTRUCT WIDENING.

STAGE 3 (SEE SHEET 19)

SHIFT TRAFFIC TO NORTH BIRCH STREET (CSAH 34) AND WEST WARE ROAD. CONSTRUCT WIDENING AND PORTION OF MEDIAN ON BIRCH STREET (CSAH 34).

STAGE 4 (SEE SHEET 20)

SHIFT WB TRAFFIC TO NORTH BIRCH STREET (CSAH 34) AND EB TRAFFIC TO SOUTH BIRCH STREET (CSAH 34). CONSTRUCT REMAINDER OF MEDIAN ON BIRCH STREET (CSAH 34).

STAGE 5 (NO SHEET)

MILL OF REMAINING EXISTING PAVEMENT. FINAL BITUMINOUS WEAR COURSE PAVING, STOP ON WARE ROAD AT BIRCH STREET (CSAH 34) TO REMAIN UNTIL SIGNAL SYSTEM COMPLETE.

NO DATE BY CKD APPR REVISION

I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

SIGNATURE:

PRINTED NAME:

BRYANT L FICEK


DATE: July 23, 2012 LIC, NO. 42802


DRAWN BY ____ DATE _____ S.A.P. 002-634-002
TKDA Proj. 14851.000
S.P.
CHECKEO BY ____ DATE _____ S.P.


11 \$10 A ENGINEERING * ARCHITECTURE * PLANNING CITY OF LINO LAKES


STAGING NARRATIVE AND NOTES
CONSTRUCTION STAGING AND TRAFFIC CONTROL
BIRCH STREET (CSAH 34)
BIRCH ST. (CSAH 34) AND WARE ROAD


SHEET 16 0F 63











	Bl	RCH ST	(CSAH	34) CC	NSTRUCTIO	N ALIGNM	ENT
NUMBER	POINT	START STATION	END STATION	LINE\CURVE LENGTH	START OF LINE COORDINATES	END OF LINE COORDINATES	LINE\CHORD DIRECTION
Li	Pl	0+00.00	4+94.02	494.02	N=139039.11 E=536182.77	N=139028.10 E=536676.67	S88*43' 21.73"E
L2	Pl	4+94.02	7+71.64	277.61	N=139028.10 E=536676.67	N=139028.76 E=536954.28	N89'51' 52.61"E
L3	PI	7+71.64	9+83.55	211.91	N=139028.76 E=536954.28	N=139028.66 E=537166.19	S89'58' 24.71"E
L4	PI	9+83.55	10+96.52	112.97	N=139028.66 E=537166.19	N=139030.61 E=537279.15	N89°00' 43.38"E
L5	PJ	10+96,52	14+98.79	402.27	N=139030.61 E=537279.15	N=139030.42 E=537681.42	S89°58′ 24.71″E
L.6	Pl	14+98.79	20+50.00	551.21	N=139030.42 E=537681.42	N=139040.35 E=538232.54	N88'58' 06.52"E

HORIZONTAL CONTROL

COORDINATE VALUES SHOWN IN THIS PLAN ARE ANOKA COUNTY COORDINATES, REFERRED TO THE NORTH AMERICAN DATUM OF 1983 (1996 ADJ.) THROUGH THE MINNESOTA STATE PLANE OORDINATE SYSTEM.

flagga							I HEREBY CERTIFY THAT BY ME OR UNDER MY DI
-8			l	<u> </u>			I AM A DULY LICENSE
<u> 11</u>			i				UNDER THE LAWS OF J
蛋			 	 			ع بحر ا
差		1	L	L	I		
*							SIGNATURE:
Ø.			4				DOTTO LA TANCE C
**		i .		1			PRINTED NAME: JAMES E.
-8			4		4DDD		DATE: 7/23/2012
×7	NO.	DATE	BY	CKD	APPR	REVISION	DATE. TILOTZOIZ

I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF ALE MATE OF MINNESOTA.

SIGNATURE:

PRINTED NAME: JAMES E. STUDENSKI


DRAWN BY DATE S.A.P. 002-634-002 TKDA Proj. 14851.000 S.P. CHECKED BY DATE S.P.



CITY OF LINO LAKES

ALIGNMENT PLAN
BIRCH STREET (CSAH 34)
BIRCH ST (CSAH 34)/WARE RD SIGNALIZATION

SHEET 21 OF 63





						SIOUX L	ANE CONS	STRUCTIO	N ALIGNMENT				
NUMBER	POINT	START STATION	P.I. STATION	END STATION	Δ Delta	DEGREE	RADIUS	TANGENT	LINE\CURVE LENGTH	START OF LINE COORDINATES	CURVE P.I. COORDINATES	END OF LINE COORDINATE	LINE\CHORD DIRECTION
L13	PI	30+00.00		30+61.63					61.63	N=140654.54 E=537137.15		N=140675.63 E=537195.06	N69*59 21.20 "E
C1	PC-PI-PT	30+61.63	30+96.96	31+31.57	20.04	28*57	200.00	35.33	69.94	N=140675.63 E=537195.06	N=140687.72 E=537228.26	N=140687.70 E=537263.60	N80*00' 28.2"E
L12	PI	31+31.57		35+40.00					426.53	N=140687.70 E=537263.60		N=140687.51 E=537672.02	S89'58' 24.71 "E

HORIZONTAL CONTROL

COORDINATE VALUES SHOWN IN THIS PLAN ARE ANOKA COUNTY COORDINATES, REFERRED TO THE NORTH AMERICAN DATUM OF 1983 (1996 ADJ.) THROUGH THE MINNESOTA STATE PLANE OORDINATE SYSTEM.

K.S	: Ł							
38.8	ŀſ				T			I
8 9								13)
2 2 2	ı	***************************************						Û
5 % E	ľ		***************************************				***************************************	
888	ı	***************************************		l				SI
# & &	ŀ						***************************************	PF
Plot D	t	NO	DATE	BY	CKD	APPR	REVISION	ĐA

I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED
BY ME OR UNDER MY DIRECT SUPERVISION AND THAT
I AM A DULY LICENSED PROFESSIONAL ENGINEER
UNDER THE LAWS OF THE TATE OF MINNESOTA.

SIGNATURE:

PRINTED NAME; JAMES E. STUDENSKI


DATE: 7/23/2012 LIC. NO. 23757


DRAWN BY _____ OATE _____ S.A.P. 002-634-002 TKDA Proj. 14851.000 S.P. CHECKEO BY _____ BATE _____ S.P.



CITY OF LINO LAKES ALIGNMENT PLAN SIOUX LANE BIRCH ST (CSAH 34)/WARE RD SIGNALIZATION

SHEET 22 0F 63





LEGEND

REMOVE BITUMINOUS PAVEMENT



REMOVE GRAVEL SURFACE


CLEAR AND GRUB (TREE) ===== REMOVE CURB & GUTTER

SAWCUT (FULL DEPTH)

NOTE:
THE CONTRACTOR SHALL VERIFY ALL
EXISTING UNDERGROUND UTILITY
LOCATIONS AND ELEVATIONS PRIOR TO
CONSTRUCTION. ALL INPLACE UTILITIES
MAY NOT BE SHOWN ON THIS PLAN &
THOSE THAT ARE SHOWN, MAY NOT BE
SHOWN IN THE EXACT LOCATIONS.

GENERAL NOTES:

- 1. DRIVEWAY REMOVAL LENGTH SHALL BE DETERMINED IN THE FIELD AS DIRECTED BY THE ENGINEER.
- 2. DRIVEWAYS SHALL BE SAWCUT TO PROVIDE A CLEAN EDGE FOR REMOVAL.
- 3. CONTRACTOR SHALL SALVAGE MAILBOX POSTS AND REINSTALL AS DIRECTED BY THE ENGINEER.
- 4. CONTRACTOR SHALL SALVAGE SIGNS AND SIGN POSTS AND REINSTALL AS DIRECTED BY THE ENGINEER.
- 5. ALL SAWCUTS SHALL BE FULL DEPTH.



1		1) i
						T .
		l				ÛN
		Ī				
	***************************************					SIG
			l			PR
NO	DATE	BY	CKD	APPR	REVISION	DA.
	NO	NO DATE	NO DATE BY	NO DATE BY CKD	NO DATE BY CKD APPR	NO DATE BY CKD APPR REVISION

PRINTED NAME: JAMES E. STUDENSKI ATE: 7/23/2012 LIC. NO. 23757


S.A.P. 002-634-002 TKDA Proj. 14851.000 S.P. S.P.





CITY OF LINO LAKES

INPLACE TOPO., UTILITIES, & REMOVAL PLAN SIOUX LANE
BIRCH ST (CSAH 34)/WARE RD SIGNALIZATION

SHEET 24 0F 63











- GUTTERLINE PROFILE ELEVATIONS DO NOT REFLECT DRAINAGE STRUCTURE SUMP.
- ALL CURB AND GUTTER IS GUTTER IN UNLESS NOTED OTHERWISE.

LEGEND:

SURFACE DRAINAGE FLOW DIRECTION.





ON 9 19 20

SIOUX LN & HOKAH DR INTERSECTION

0	10	20	40
	934	2005	

NO DATE BY CKD APPR REVISION

I HEREBY CERTIFY THAT THIS PLAN WAS PREPARE
BY ME OR UNDER MY DIRECT SUPERVISION AND THAT
I AM A DULY LICENSED PROFESSIONAL ENGINEE!
UNDER THE LAWS OF THE MATE OF MINNESOTA

SIGNATURE:
PRINTED NAME; JAMES E. STUDENSKI

DATE: 1/23/2012 LIC. NO. 23757

S.A.P. 002-634-002
TKDA Proj. 14851.000
S.P.


KED BY ____ DATE ____ S.P.

TIKIDA
ENGINEERING - ARCHITECTURE - PLANNING

CITY OF LINO LAKES

INTERSECTION DETAIL
SIOUX LANE
BIRCH ST (CSAH 34)/WARE RD SIGNALIZATION

SHEET 28 OF 63



PROJECT LOCATION AND DESCRIPTION

THE PROJECT (S.A.P. 002-634-002) IS LOCATED ON BIRCH STREET FROM APPROXIMATELY 450 FEET EAST OF HODGSON ROAD TO APPROXIMATELY 2000 FEET TO THE EAST. ALSO, THE PROJECT INLCUDES SIOUX LANE FROM 350 FEET EAST OF SIOUX LOOKOUT TO HOKAY DRIVE AS SHOWN ON THE TITLE SHEET AND GENERAL LAYOUT (SHEETS 1-2).

THE PROJECT INCLUDES:

- GRADING
 BITUMINOUS MILL & OVERLAY
- ADA IMPROVEMENTS
- TRAFFIC SIGNALS
- TURN LANE CONSTRUCTION
- MISCELLANEOUS STORM SEWER, CULVERT, AND DRAINAGE STRUCTURE
- REPAIRS AND REPLACEMENTS
- MINOR DITCH GRADING
- TEMPORARY EROSION AND SEDIMENT CONTROL
- PERMANENT EROSION CONTROL AND TURF ESTABLISHMENT

THE APPROXIMATE CONSTRUCTION TIMELINE IS JULY 2012 TO DECEMBER 2012.

PROJECT CONTACTS / RESPONSIBLE PARTIES

IN ACCORDANCE WITH MN/DOT SPEC. 2573.3A1, THE CONTRACTOR WILL PROVIDE A CERTIFIED EROSION CONTROL SUPERVISOR IN GOOD STANDING WHO IS KNOWLEDGEABLE AND EXPERIENCED IN THE APPLICATION OF EROSION PREVENTION AND SEDIMENT CONTROL BEST MANAGEMENT PRACTICES. THE EROSION CONTROL SUPERVISOR IS INCIDENTAL. THE EROSION CONTROL SUPERVISOR SHALL BE AVAILABLE TO BE ON SITE WITHIN 24 HOURS AT ALL TIMES FROM INITIAL DISTURBANCE TO FINAL STABILIZATION, AS WELL AS PERFORMING THE DUTIES LISTED IN MN/DOT SPEC. 2573.

THE ANOKA COUNTY INSPECTOR AND THE CITY EROSION CONTROL SUPERVISOR ARE RESPONSIBLE FOR IMPLEMENTATION OF THE SWPPP AND INSTALLATION, INSPECTION, AND MAINTENANCE OF THE EROSION PREVENTION AND SEDIMENT CONTROL BMPS BEFORE AND DURING CONSTRUCTION UNTIL THE NOTICE OF TERMINATION HAS BEEN FILED WITH THE MPCA.

THE CITY OF LINO LAKES WILL BE RESPONSIBLE FOR THE LONG-TERM OPERATION AND MAINTENANCE OF THE PERMANENT STORM WATER MANAGEMENT SYSTEM.

LINO LAKES ENGINEER

JASON WEDEL 600 TOWN CENTER PARKWAY LINO LAKES, MN 55014

(651) 982-2430 MPCA CONTACT

MPCA CONTACT SHAWN NELSON MPCA COUNTY STAFF CONTACT (651) 757-2604 (651) 982-2245

SWPPP DESIGNER
FRANK TICKNOR TKDA
DESIGN OF SWPPP
CERTIFICATION

EXPIRES MAY 31, 2014

CITY EROSION CONTROL SUPERVISOR

600 TOWN CENTER PARKWAY

LINO LAKES, MN 55014

(661) 726-7925

TIM PAYNE

CONTRACTOR EROSION CONTROL SUPERVISOR

MPCA 24-HR EMERGENCY NOTIFICATION (STATE DUTY OFFICER) (651) 649-5451

(800) 422-0798

ENVIRONMENTALLY SENSITIVE AREAS

THERE ARE NO ENVIRONMENTALLY SENSITIVE AREAS WITHIN THE PROJECT LIMITS. NO WETLANDS EXIST WITHIN THE PROJECT LIMITS. THERE ARE NO CALCAREOUS FENS WITHIN THE PROJECT LIMITS. THIS PROJECT IS NOT LOCATED IN AN AREA THAT IS KNOWN TO BE ACTIVE KARST.

ENVIRONMENTAL REVIEW

THERE ARE NOT STORM WATER MITIGATION MEASURES REQUIRED AS A RESULT OF AN ENVIRONMENTAL, ARCHEOLOGICAL, OR AGENCY REVIEW.

OIL TYPES

SOIL TYPES TYPICALLY FOUND ON THIS PROJECT ARE SILTY SAND AND SAND WITH SILT.

SWPPP TRAINING REQUIREMENTS

THIS SWPPP WAS PREPARED BY TKDA PERSONNEL THAT ARE CERTIFIED IN THE DESIGN OF CONSTRUCTION SWPPPS, COPIES OF THE CERTIFICATIONS ARE ON FILE WITH MN/DOT AND ARE AVAILABLE UPON REQUEST. THE CONTRACTOR IS RESPONSIBLE FOR PROVIDING A CERTIFIED EROSION CONTROL SUPERVISOR THAT IS RESPONSIBLE FOR OVERSEEING THE

OF CERTIFICATION AT THE PRECONSTRUCTION MEETING AND WILL NOT BE ALLOWED TO COMMENCE WORK UNTIL PROOF OF CERTIFICATION HAS BEEN PROVIDED TO THE PROJECT ENGINEER.

LAND FEATURE CHANGES *

TOTAL DISTURBED SURFACE AREA:

2.16 ACRES

TOTAL EXISTING IMPERVIOUS SURFACE AREA: 0.46 ACRES

TOTAL POST-CONSTRUCTION IMPERVIOUS SURFACE AREA:

0.85 ACR

TOTAL POST-CONSTRUCTION NET CHANGE IN IMPERVIOUS SURFACE AREA: 0.39 ACRES

* DOES NOT INCLUDE MILLED OR RECLAIMED SURFACE AREAS.

LOCATION OF SWPPP REQUIREMENTS

THE REQUIRED SWPPP ELEMENTS MAY BE LOCATED IN MANY PLACES WITHIN THE PLAN SET, AS WELL AS IN THE SPECIAL PROVISIONS, MN/DOT SPEC. BOOK (2005 EDITION), OR ON FILE WITH MN/DOT. THE NOTES AND TABLE BELOW ARE INTENDED TO BE A QUICK REFERENCE FOR THE CONTRACTOR AND PROJECT ENGINEER TO USE IN THE FIELD. THERE MAY BE ADDITIONAL REQUIRED SWPPP ELEMENTS INCLUDED ON THE PROJECT THAT ARE NOT LISTED ON THIS SHEET.

LOCATION OF SWPPP REQUIREMENTS	IN PR	DJECT	PLAN
DESCRIPTION	LC	CATIC	N
ESTIMATED QUANTITIES	SHEET	NOS.	3-4
SOILS AND CONSTRUCTION NOTES, STANDARD PLATES	SHEET	NO.	5
EROSION CONTROL AND TURF ESTABLISHMENT	SHEET	NOS.	35-37
INPLACE TOPOGRAPHY, UTILITIES, AND REMOVALS	SHEET	NOS.	23-24
CONSTRUCTION PLANS	SHEET	NOS.	25-27
DRAINAGE PLANS	SHEET	NO.	32
DRAINAGE PROFILES AND TABULATIONS	SHEET	NO.	33

INSPECTIONS AND MAINTENANCE

THE EROSION CONTROL SUPERVISOR MUST ROUTINELY INSPECT THE ENTIRE CONSTRUCTION SITE ONCE EVERY 7 DAYS DURING ACTIVE CONSTRUCTION AND WITHIN 24 HOURS AFTER A RAINFALL EVENT GREATER THAN 0.5 INCHES IN 24 HOURS, THE EROSION CONTROL SUPERVISOR SHALL BE AVAILABLE TO BE ON SITE WITHIN 24 HOURS AT ALL TIMES FROM INITIAL DISTURBANCE TO FINAL STABILIZATION, AS WELL AS PERFORMING THE DUTIES LISTED IN MN/DOT SPEC. 2573.

ALL EROSION AND SEDIMENT CONTROL BMPS MUST BE INSPECTED BY THE CONTRACTOR TO ENSURE INTEGRITY AND EFFECTIVENESS. ALL NONFUNCTIONAL BMPS MUST BE REPAIRED, REPLACED, OR SUPPLEMENTED WITH FUNCTIONAL BMPS AS DIRECTED BY THE EROSION CONTROL SUPERVISOR OR THE PROJECT ENGINEER.

ALL INSPECTIONS AND MAINTENANCE CONDUCTED DURING CONSTRUCTION MUST BE RECORDED IN WRITING, AND THESE RECORDS MUST BE RETAINED WITH THE SWPPP IN ACCORDANCE WITH PART III.D OF THE NPDES PERMIT AND KEPT ON SITE DURING CONSTRUCTION.

SITE PLANS REQUIREMENT AREAS

THE CONTRACTOR WILL PREPARE AND SUBMIT A SITE PLAN FOR THE ENGINEER'S APPROVAL AS PER MINIOT SPEC. 1717.2E FOR CONCRETE MANAGEMENT WORK NEAR ENVIRONMENTALLY SENSITIVE AREAS, AREAS IDENTIFIED IN THE PLANS AS "SITE PLAN REQUIREMENT AREA," ANY WORK THAT WILL REQUIRE DEWATERING, THE STAGING OF INLET PROTECTION DEVICES, AND AS REQUESTED BY THE ENGINEER. ALL SITE PLANS MUST BE SUBMITTED TO THE ENGINEER IN WRITING. THE CONTRACTOR SHALL ALLOW A MINIMUM OF SEVEN DAYS FOR MINIOOT TO REVIEW AND APPROVE SITE PLAN SUBMITTALS. THE CONTRACTOR WILL NOT BE ALLOWED TO COMMENCE WORK FOR WHICH A SITE PLAN IS REQUIRED UNTIL APPROVAL HAS BEEN GRANTED BY THE ENGINEER. THE CONTRACTOR WILL NOT BE GIVEN ANY EXTRA TIME IN THE CONTRACT DUE TO THE UNTIMELY SUBMITTAL OF A SITE PLAN.

DRAINAGE COMPUTATIONS

DATE: 7/23/2012

COMPUTATIONS ARE KEPT ON FILE WITH THE CITY OF LINO LAKES. CHANGES MADE IN THE FIELD MUST BE DISCUSSED WITH THE PROJECT ENGINEER, APPROVED BY THE CITY ENGINEER, AND NOTED IN THE CONTRACTOR'S CONSTRUCTION LOCKED.

LIC. NO. 23757

CONSTRUCTION NOTES

CONSTRUCTION SHALL BE GOVERNED BY THE MN/DOT 2005 SPEC. BOOK AND THE SPECIAL PROVISIONS. THE CONTRACTOR MUST KEEP THE SWPPP, ALL CHANGES TO IT, AND INSPECTION AND MAINTENANCE RECORDS AT THE SITE DURING CONSTRUCTION.

POLLUTION PREVENTION MANAGEMENT

THE CONTRACTOR WILL IMPLEMENT THE POLLUTION PREVENTION MANAGEMENT MEASURES AS DIRECTED IN THE NPDES PERMIT, PART IV.F AS IT PERTAINS TO SOLID WASTE, HAZARDOUS MATERIALS, EXTERNAL TRUCK WASHING, BITUMINOUS PAVING MACHINE, AND CONCRETE TRUCK WASHOUT. THESE MANAGEMENT MEASURES FOR POLLUTION PREVENTION WILL BE STRICTLY ENFORCED.

THE EROSION CONTROL SUPERVISOR SHALL MAKE A SPILL RESPONSE PLAN BEFORE THE APPLICATION OF ANY CHEMICAL THAT MAY BE HARMFUL TO THE ENVIRONMENT. ALL SPILLS WILL BE CLEANED UP IMMEDIATELY UPON DISCOVERY, SPILLS LARGE ENOUGH TO REACH THE STORM CONVEYANCE SYSTEM MUST BE REPORTED TO THE MPCA STATE DUTY OFFICER. THE CONTRACTOR MUST HAVE A SPILL KIT ON SITE AT ALL TIMES (INCIDENTAL).

SOLID WASTE SUCH AS COLLECTED SEDIMENT, ASPHALT AND CONCRETE MILLINGS, FLOATING DEBRIS, PAPER, PLASTIC, FABRIC, CONSTRUCTION AND DEMOLITION DEBRIS, AND OTHER WASTES MUST BE DISPOSED OF PROPERLY AND MUST COMPLY WITH MPCA DISPOSAL REQUIREMENTS. THE CONTRACTOR IS RESPONSIBLE FOR CREATING AND FOLLOWING A WRITTEN DISPOSAL PLAN FOR ALL WASTE MATERIALS. THE PLAN WILL INCLUDE HOW THE MATERIAL WILL BE DISPOSED OF AND THE LOCATION OF THE DISPOSAL SITE. THIS PLAN MUST BE SUBMITTED TO THE ENGINEER.

THE CONTRACTOR MUST USE METHODS AND OPERATIONAL PROCEDURES THAT PREVENT DUST, PARTICLES, SAW CUT SLURRY, CONCRETE WASTES, BITUMINOUS GRINDINGS, CUTTINGS, MILLINGS, AND OTHER WASTE FROM LEAVING MN/DOT RIGHT-OF-WAY, DEPOSITING IN EXISTING OR FUTURE VEGETATED AREAS, OR ENTERING STORM WATER CONVEYANCE SYSTEMS, INCLUDING INLETS AND CURB FLOW LINES.

CONCRETE CRUSHING, PECKING, SAWING, AND GRINDING WILL REQUIRE DUST CONTROL USING WATER MISTS (INCIDENTAL), AND ALL CONCRETE PUMPING, WASHOFF, AND WASHOUT AREAS WILL NEED TO BE DESIGNATED AND KEPT FUNCTIONAL SOMEPLACE INSIDE THE PROJECT LIMITS. LEAD PAINT CHIPS MUST NOT COME INTO CONTACT WITH SOILS UNLESS IT IS THE INTENT OF THE CONTRACTOR TO HAUL OFF ALL CONTAMINATED SOILS.

CHEMICALS SUCH AS OIL, FUEL, FERTILIZER, AND PAINT MUST BE PROPERLY STORED, INCLUDING SECONDARY CONTAINMENT, TO PREVENT SPILLS, LEAKS, OR OTHER DISCHARGE. RESTRICTED ACCESS TO STORAGE AREAS MUST BE PROVIDED TO PREVENT VANDALISM. STORAGE AND DISPOSAL OF HAZARDOUS WASTE MUST BE IN COMPLIANCE WITH MPCA REGULATIONS. THE CONTRACTOR WILL BE REQUIRED TO UPDATE THE SWPPP FOR PORTABLE RESTROOM PLACEMENT, REFUELING METHODS (INCLUDING SPILL KITS), AND SECONDARY CONTAINMENT OF STATIONARY MACHINES WITH FLUIDS. PORTABLE RESTROOM FACILITIES WILL BE ANCHORED TO PREVENT TIPPING.

TRUCK WASHING AND CONCRETE WASHOUT SHALL TAKE PLACE IN A FIELD OR COMMERCIALLY ENGINEERED LEAK-PROOF CONTAINMENT FACILITY OR IMPERMEABLE LINER THAT PREVENTS RUNOFF ONTO ADJACENT SOILS. LOCATION OF WASHOUT AREAS MUST BE IDENTIFIED BY SIGNAGE, MUST BE AT LEAST 200 FEET FROM ENVIRONMENTALLY SENSITIVE AREAS, AND MUST BE SHOWN ON AN ENGINEER-APPROVED SITE PLAN. IF DEEMED NECESSARY BY THE PROJECT ENGINEER, THE CONTENTS SHALL BE DISPOSED OF AT AN APPROPRIATE FACILITY OFF SITE.

BURNING OF ANY MATERIAL IS NOT ALLOWED WITHIN THE PROJECT BOUNDARY.

CONSTRUCTION PHASE POLLUTANT SOURCES ANTICIPATED AT THIS SITE ARE DISTURBED (BARE) SOIL; SEDIMENT; VEHICLE FUELS AND LUBRICANTS; CHEMICALS ASSOCIATED WITH CONSTRUCTION; BITUMINOUS GRINDINGS, CUTTINGS, AND MILLINGS; CONSTRUCTION-GENERATED LITTER AND DEBRIS; AND CONCRETE WASTE. WITHOUT ADEQUATE CONTROL, THERE IS POTENTIAL FOR EACH TYPE OF POLLUTANT TO BE TRANSPORTED BY STORM WATER.

IF SEDIMENT DEPOSITS IN A WATER OF THE STATE (AS DEFINED IN THE NPDES

PERMIT), THE SEDIMENT MUST BE REMOVED WITHIN SEVEN DAYS.

EROSION PREVENTION PRACTICES

THE CONTRACTOR MUST PLAN FOR AND IMPLEMENT CONSTRUCTION PRACTICES THAT MINIMIZE EROSION, PHASED CONSTRUCTION SHALL BE USED TO MINIMIZE SEDIMENT TRANSPORT.

DITCHES AND EXPOSED SOILS MUST BE KEPT IN AN EVEN, ROUGH GRADED CONDITION IN ORDER TO BE ABLE TO APPLY EROSION CONTROL MULCHES AND BLANKETS, ALL EXPOSED SOIL AREAS MUST BE TEMPORARILY OR PERMANENTLY STABILIZED NO MORE THAN SEVEN DAYS AFTER CONSTRUCTION ACTIVITY ON THAT PORTION OF THE SITE HAS TEMPORARILY OR PERMANENTLY CEASED. IN MANY INSTANCES, THIS WILL REQUIRE STABILIZATION TO OCCUR MORE THAN ONCE DURING ROUGH GRADING. RAPID STABILIZATION METHOD 1, 2, 3, OR 4 WILL BE USED TO PROVIDE TEMPORARY COVER IN THESE AREAS AS APPROPRIATE.

THE NORMAL WETTED PERIMETER OF ANY TEMPORARY OR PERMANENT DRAINAGE DITCH OR SWALE THAT DRAINS WATER FROM OR AROUND THE CONSTRUCTION SITE MUST BE STABILIZED WITHIN 200 FEET FROM THE PROPERTY EDGE OR POINT OF DISCHARGE INTO ANY SURFACE WATER. STABILIZATION MUST BE COMPLETED WITHIN 24 HOURS OF CONNECTION TO A SURFACE WATER, EXISTING GUTTER, STORM SEWER INLET, DRAINAGE DITCH, OR OTHER STORM WATER CONVEYANCE SYSTEM ACCORDING TO MN/DOT SPEC 1717-2A2, RAPID STABILIZATION METHOD 4 WILL BE USED TO STABILIZE THESE AREAS. STABILIZATION OF THE REMAINING PORTIONS OF THE DITCH OR SWALE MUST BE COMPLETED WITHIN SEVEN DAYS SINCE THE PROJECT IS WITHIN 1 MILE OF AND DRAINS TO A SPECIAL WATER, DISC ANCHORED MULCH AND HYDRAULIC SOIL STABILIZERS ARE NOT ALLOWED TO BE USED FOR PERMANENT DITCH STABILIZATION.

PIPE OUTLETS INTO SURFACE WATERS MUST BE STABILIZED WITH TEMPORARY OR PERMANENT ENERGY DISSIPATION WITHIN 24 HOURS OF BEING CONSTRUCTED.

UNDISTURBED GRASS BUFFERS ON INSLOPES SHALL REMAIN IN PLACE AS PERIMETER CONTROL.

ALL EXPOSED SOIL AREAS WILL BE STABILIZED PRIOR TO THE ONSET OF WINTER. ANY WORK STILL BEING PERFORMED WILL BE SNOW MULCHED, SEEDED, OR BLANKETED WITHIN THE TIME FRAMES IN THE NPDES PERMIT.

ALL TEMPORARY TOPSOIL BERMS SHALL BE STABILIZED AS FOLLOWS:

- BETWEEN APRIL 1 AND AUGUST 31, SEED WITH MIXTURE 150.
- BETWEEN SEPTEMBER 1 AND MARCH 31, SEED WITH SEED MIXTURE 150 AND TOP WITH RAPID STABILIZATION 2.

(1 OF 2)

IMPLEMENTATION OF THE SWPPP. THE CONTRACTOR MUST PROVIDE PROOF

NO DATE BY CKD APPR REVISION

I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE JATE OF MINNESOTA.

SIGNATURE:

PRINTED NAME: JAMES E. STUDENSKI

DRAWN BY DATE S.A.P. 002-634-002
TKDA Proj. 14851.000
S.P.
CHECKED BY DATE S.P.



CITY OF LINO LAKES

STORM WATER POLLUTION
PREVENTION PLAN NOTES
BIRCH ST (CSAH 34)/WARE RD SIGNALIZATION

SHEET 30 OF 63

Fig. Under Underschaft.
Fig. Under Underschaft.
Fig. Under Kigner Kind.
Fig. D. Sterkfund.
Fig. D. Sterkfund

SEDIMENT CONTROL PRACTICES MUST BE ESTABLISHED ON ALL DOWN-GRADIENT PERIMETERS BEFORE ANY UP-GRADIENT LAND DISTURBING ACTIVITIES BEGIN. THESE PRACTICES SHALL REMAIN IN PLACE UNTIL FINAL STABILIZATION HAS BEEN ESTABLISHED. SEE THE STANDARD PLANS FOR DETAILS. SEDIMENT CONTROL PRACTICES MUST MINIMIZE SEDIMENT ENTERING SURFACE WATERS, INCLUDING CURB AND GUTTER SYSTEMS AND STORM SEWER INLETS. ALL STORM DRAIN INLETS MUST BE PROTECTED BY APPROPRIATE BMPS DURING CONSTRUCTION UNTIL ALL SOURCES WITH POTENTIAL DISCHARGE TO THE INLET HAVE BEEN STABILIZED. SEDIMENT REACHING SURFACE WATERS MUST BE REMOVED WITHIN SEVEN DAYS,

PERIMETER CONTROL SUCH AS SILT FENCE OR FILTER LOGS SHALL BE LOCATED ON THE CONTOUR TO CAPTURE OVERLAND, LOW-VELOCITY SHEET FLOWS DOWN GRADIENT OF ALL EXPOSED SOILS AND PRIOR TO DISCHARGING TO SURFACE WATERS, WITH THE BMP J-HOOKED AT A MAXIMUM OF 100-FOOT INTERVALS, AND SHALL CONTAIN NO MORE THAN 1/4 ACRE OF DRAINAGE AREA, PERIMETER CONTROL MUST BE REPAIRED OR REPLACED WHEN IT BECOMES NONFUNCTIONAL OR THE SEDIMENT REACHES ONE-THIRD OF THE HEIGHT OF THE BMP. REPAIRS MUST BE MADE WITHIN 24 HOURS OF DISCOVERY AND ARE CONSIDERED

DITCH CHECKS WILL BE PLACED AS INDICATED ON THE PLANS DURING ALL PHASES OF CONSTRUCTION, TEMPORARY DITCH CHECKS WILL CONSIST OF USING ROCK DITCH CHECKS, BIOLOGS, AND ROCK WEEPERS IN FRONT OF CULVERT INLETS, IN LIEU OF REMOVING TEMPORARY DITCH CHECKS, THE ROCK MAY BE PUSHED INTO THE GROUND, FILTER LOGS WILL BE PLACED DURING PERMANENT TURF ESTABLISHMENT AT THE INTERVALS

SEDIMENT DAMAGE FROM SOIL STOCKPILES WILL BE MINIMIZED BY PLACING A ROW OF HEAVY DUTY OR SUPER DUTY SILT FENCE A MINIMUM DISTANCE OF 5 FEET FROM THE TOE OF SLOPE, IF THERE IS NOT ADEQUATE PROJECT AREA TO PLACE THE SILT FENCE MORE THAN 5 FEET FROM THE TOE, THE CONTRACTOR MAY SUBMIT AN ALTERNATIVE FOR APPROVAL BY THE PROJECT ENGINEER, SOIL STOCKPILES CANNOT BE PLACED IN SURFACE WATERS, INCLUDING STORM WATER CONVEYANCES SUCH AS CURB AND GUTTER SYSTEMS OR DITCHES.

STORM SEWER INLETS WILL BE PROTECTED AT ALL TIMES WITH THE APPROPRIATE INLET PROTECTION FOR EACH SPECIFIC PHASE OF CONSTRUCTION, INLET PROTECTION DEVICES MAY NEED TO BE PLACED MULTIPLE TIMES IN THE SAME LOCATION OVER THE LIFE OF THE CONTRACT. INLET PROTECTION DEVICES WILL BE PAID FOR ONCE PER INLET REGARDLESS OF THE NUMBER OF TIMES THE BMP IS PLACED, ALL STORM SEWER INLET PROTECTION DEVICES WILL BE KEPT IN GOOD FUNCTIONAL CONDITION AT ALL TIMES. IF THE PROJECT ENGINEER DEEMS AN INLET PROTECTION DEVICE TO BE NONFUNCTIONAL. IN POOR CONDITION, INEFFECTIVE, OR NOT APPROPRIATE FOR THE CURRENT CONSTRUCTION ACTIVITIES, IT WILL BE REPLACED WITH A SUITABLE ALTERNATIVE AT NO COST TO MN/DOT.

THE CONTRACTOR WILL PLACE WOOD CHIP PADS, SLASH MULCH PADS, OR ROCK PADS AT MAJOR VEHICLE EXIT LOCATIONS TO MINIMIZE VEHICLE TRACKING OF SEDIMENT ONTO PAVED SURFACES (INCIDENTAL), PADS WILL BE SUFFICIENTLY SIZED AND MAINTAINED TO PREVENT TRACK OUT. STREET SWEEPING MUST BE USED IF SEDIMENT IS BEING TRACKED OFF THE CONSTRUCTION SITE (INCIDENTAL), TRACKED SEDIMENT MUST BE REMOVED WITHIN 24 HOURS OF DISCOVERY, PAVEMENT SHALL BE LIGHTLY WETTED PRIOR TO SWEEPING.

TEMPORARY DEWATERING ACTIVITIES MAY BE REQUIRED FOR THE ROADWAY CONSTRUCTION AND UTILITY WORK. A WATER APPROPRIATIONS PERMIT WILL BE REQUIRED FROM THE MNDNR FOR CONSTRUCTION DEWATERING EXCEEDING 10,000 GALLONS PER DAY. THE CONTRACTOR WILL BE RESPONSIBLE FOR OBTAINING THIS PERMIT.

TEMPORARY DEWATERING RELATED TO THE CONSTRUCTION ACTIVITY THAT MAY HAVE TURBID OR SEDIMENT-LADEN DISCHARGE WATER MUST BE DISCHARGED TO A TEMPORARY SEDIMENT BASIN ON THE PROJECT SITE OR AN ACCEPTABLE ALTERNATIVE, IF THE WATER CANNOT BE

DISCHARGED TO A SEDIMENT BASIN PRIOR TO ENTERING RECEIVING WATERS, IT MUST BE TREATED WITH THE APPROPRIATE BMPS SUCH THAT THE DISCHARGE DOES NOT ADVERSELY AFFECT THE RECEIVING WATER OR DOWNSTREAM LANDOWNERS, THE CONTRACTOR MUST ENSURE THAT DISCHARGE POINTS ARE ADEQUATELY PROTECTED FROM EROSION AND SCOUR, THE DISCHARGE MUST BE DISPERSED OVER NATURAL ROCK RIPRAP, SAND BAGS, PLASTIC SHEETING, OR OTHER ACCEPTED ENERGY DISSIPATION MEASURES, ADEQUATE SEDIMENTATION CONTROL MEASURES ARE REQUIRED FOR DISCHARGE WATER THAT CONTAINS SUSPENDED SOLIDS, ALL DEWATERING REQUIRES A SITE PLAN TO BE SUBMITTED TO THE ENGINEER FOR APPROVAL PRIOR TO COMMENCING WORK, ACCORDING TO MN/DOT SPEC. 1717.2E.

FINAL STABILIZATION

THE CONTRACTOR MUST ENSURE FINAL STABILIZATION OF THE SITE. FINAL STABILIZATION SHALL INCLUDE A MINIMUM OF 70% VEGETATION ESTABLISHMENT (100% STABILIZED) ON ALL PERVIOUS AREAS.

ALL TEMPORARY EROSION CONTROL MEASURES AND BMPS MUST BE REMOVED AS PART OF THE FINAL STABILIZATION, UNLESS DIRECTED OTHERWISE BY THE OWNER OR ENGINEER.

THE PERMITEES MUST SUBMIT A NOTICE OF TERMINATION TO THE MPCA WITHIN 30 DAYS OF FINAL STABILIZATION OR OF TRANSFERRING PERMIT RESPONSIBILITY TO ANOTHER OWNER OR OPERATOR.

(2 OF 2)


PRINTED NAME: JAMES E. STUDENSKI DATE: 7/23/2012 LIC. NO. 23757

S.A.P. 002-634-002 TKDA Proj. 14851.000 ESIGN BY S.P. S.P. HECKED BY___



CITY OF LINO LAKES

31



	DRAINAGE TABULATION																							
				COORDIN	IATES (A)				NEW	STRUCTU	RE CONST	RUCTION		PIPE SEV	ER DESIG	N 3006 (G)	APRON (F)	TRASH	RIP RAP	<u> </u>	DI	RAINS TO)	T
STRUCTURE OF						OUTLET	F 8 CAST			PAY HEI	HT DESIGI	N	CONTROL		(H)		24"	GUARD	CLIII	GUIDE	STRUC.	SLOPE		
APRON INLET POINT NO.	ALIGNMENT	STATION	OFFSET	х	Y	ELEVATION (A)	ASS (C		402 (B)	N	48-4020	60-4020	STRUCTURE (BAFFLED WEIR)	15" RC CL II	18" RC CL II	24" RC CL II	RC	24"	(E)	POST TYPE B	OR APRON OUTLET POINT NO.	OF PIPE %	INLET ELEV.	NOTES
							TYPE	EACH	LIN FT	LIN FT	LIN FT	LIN FT	EACH	LIN FT	LIN FT	LIN FT	EACH	EACH	CUYD	EACH		<u> </u>		<u> </u>
5006	BIRCH	10+56.26	83.58 LT	537237.46	139113.48	895.74	B-17	1	<u> </u>	4.1				45							5000	0.30	895.60	(A)
5005	BIRCH	10+60.66	60.69 RT	537244,34	138969,31	896,00	B-17	1	<u> </u>	3.8				100				1			5000	0.40	895.60	(A)
5000	BIRCH	10+63.56	39.49 LT	537245.51	139069.52	895.60	A-7D	1	<u> </u>		4.9	ļ	···········	282		1		1			5001	0.31	894.73	
5007	BIRCH	13+48.16	15.18 RT	537530.78	139015.31	896.75	B-17	1	ļ	4.0		ļ	·	55		<u> </u>					5001	2.15	895.55	
5001	BIRCH	13+45.11	41.09 LT	537527.76	139071,58	894.63	B-17	11		ļ	6.0			<u> </u>	370	<u> </u>		<u> </u>	!		5002	0.34	893.37	(A)
5008	BIRCH	17+16,72	18,20 RT	537899.64	139016.15	894.90	B-17	1		4.0				54				<u> </u>	l		5002	1.85	893.90	(A)
5002	BIRCH	17+15.66	36.99 LT	537897.59	139071.31	893.27	B-17	1		ļ	5.3			<u> </u>	<u> </u>	188		<u> </u>	<u> </u>		5014	0.29	892.73	(A)
5009	BIRCH	19+86.52	23.62 RT	538169.50	139015,59	893,59	B-17	1		4,0				68				l			5003	1.24	892.75	(A)
5014	BIRCH	19+03.56	22.77 LT	538085,71	139060.48	892.74	B-17	1			5.1	ļ				38				<u> </u>	5003	0.29	892.62	(A)
5003	BIRCH	19+41.48	26.73 LT	538123.56	139065.12	892.63	A-7D	1		ļ		5,1				46		<u> </u>		<u> </u>	5004	0.30	892.48	(A)
5004	BIRCH	19+45.95	72.79 LT	538127.20	139111,25	892,48											1	1	5.0	. 1				
6010	BIRCH	19+57,77	121.19 LT	538138,14	139159.85	892.50							1			<u> </u>		1						(C)
6011	BIRCH	20+08.03	158.81 LT	538187.72	139198.37	892.50							1									1		(C)
5015	SIOUX	32+67.37	14.04 RT	537399.39	140673,60	890,14	C-1	1	3,9			1		38				1			5016	0,30	890.03	(A)
5016	SIOUX	32+78.11	20.98 LT	537410.14	140708.62	889.93	C-1	1	4.0					39							EX CB	0.30	889.81	(A)
EXISTING CB	SIOUX	33+14.45	32.81 LT	537446.48	140720.42	886.15 (EX)	<u> </u>					1		<u></u>	1									
TOTALS								12	8	20	21	5	2	681	370	272	1	1	5	1				

(A) STATION, OFFSET, COORDINATES, AND ELEVATIONS GIVEN TO CENTER OF CASTING OR END OF CONCRETE APRON UNLESS OTHERWISE NOTED.

(B) CITY OF LINO LAKES STANDARD DRAWING NUMBER

(C) SEE DRAINAGE DETAILS SHEET 38.

(D) ALL STRUCTURES WITH B - 17 CASTINGS MUST HAVE A TOP OPENING OF 30".

(E) GRANULAR FILTER BLANKET OR GEOTEXTILE FILTER MATERIAL REQUIRED (CONSIDERED INCIDENTAL). SEE MN/DOT STANDARD PLATE 3133.

(F) TIE ALL JOINTS FROM LAST STRUCTURE TO APRON END. FURNISHING AND INSTALLING PIPE TIES CONSIDERED INCIDENTAL. SEE MN/DOT STANDARD PLATE 3145.

(G) LENGTH GIVEN TO END OF APRON.

(H) CLASS "C" BEDDING FOR RC PIPE UNLESS OTHERWISE SPECIFIED.

		CAS	TING ASSEMBLI	ES		
ASSEMBLY	RING OR FRAME CASTING	COVER OR GRATE CASTING	CURB BOX	MN/DOT STANDARD PLATE NO.	QUANTITY	REMARKS
	806			4125		
B - 17		816		4154	8	CATCH BASIN
			825	4134	1	
	808	806		4101		
A - 7D		715		4110	2	MANHOLE
			N/A		1	
	R-3250-A					
C - 1		R-3250-A			2	LINO LAKES CATCH BASIN
			R-3250-A		1	OATOIS BAOIN

3 8			l	 		
age Bus						
Š						
2 5				 		
Ş			1	 		
200						
X	NO	DATE	BY	APPR	REVISION REVISION	

DATE: 7/23/2012

__ LIC. NO. 23757


DRAWN BY DATE	S.A.P. 002-634-002
	TKDA Proj. 14851.000
	S.P.
CHECKED BY DATE	S.P.





DRAINAGE PLAN AND TABULATION
BIRCH ST (CSAH 34)
BIRCH ST (CSAH 34)/WARE RD SIGNALIZATION

CITY OF LINO LAKES


SHEET 32 0F 63









LOCATION OF SILT FENCE AT TOE OF ROADWAY EMBANKMENT






DESIGN GUIDELINES: TO PROTECT AREAS FROM SHEET FLOW. MAXIMUM CONTRIBUTING AREA: 1 ACRE.



SILT FENCE, J-HOOK INSTALLATION




						I HEREBY CERTIFY THAT THIS PLAN WAS PREPAR BY ME OR UNDER MY DIRECT SUPERVISION AND TH
						I AM A DULY LICENSED PROFESSIONAL ENGINE UNDER THE LAWS OF THE MATE OF MINNESON
			<u> </u>			SIGNATURE: STATE C STATE C
						PRINTED NAME: JAMES E. STUDENSKI
NО	DATE	ВΥ	CKD	APPR	REVISION	DATE: 7/23/2012 LIC. NO. 23757


ARED THAT WEER OTA. DESIGN BY DATE S.A.P. 002-634-002 TKDA Proj. 14851.000 S.P.				
DESIGN BY DATE S.P.	THAT	DRAWN BY	DATE	S.A.P. 002-634-002
		DESIGN BY	DATE	
CHECKED BY DATE S.P.		CHECKED BY	DATE	S.P.





EROSION CONTROL DETAILS BIRCH ST (CSAH 34)/WARE RD SIGNALIZATION

CITY OF LINO LAKES SHEET 35 OF 63










	EARTH	WORK SUMM	ARY				
		EXCAV	EMBANKMENT				
LOCATION	COMMON (E.V.)	TOPSOIL (E.V.)	POND SUBCUT (E.V.) (A)	COMMON CHANNEL (E.V.) (A)	SUITABLE GRADING (C.V.)	TOPSOIL (C.V.)	
	CUYD	CU YD	CU YD	CU YD	CU YD	CUYD	
BIRCH STREET	840	·				370	
SIOUX LANE	257					49	
POND 10		73	18	252			
POND 20		220	97	754	500		
TOTALS	1097	293	115	1006	500	554	

(A) POND EXCAVATION. NO ATTEMPT HAS BEEN MADE TO DETERMINE THE TYPE OF MATERIAL TO BE EXCAVATED.



EXCAVATION (CU YD) TOPSOIL EXCAVATION (1) COMMON EXCAVATION 1390 (EV) · (BID ITEM) └─ COMMON EXCAVATION — 1097 POND SUBCUT COMMON CHANNEL

TOPSOIL MATERIAL NEEDED ---- 428 / 1.3 = 329 (CV) --

554 (CV) TOPSOIL EMBANKMENT

EMBANKMENT (CU YD)

115 1006

COMMON CHANNEL EXCAVATION — 650 / 1.3 = 500 (CV) — 500 (CV) SUITABLE GRADING EMBANKMENT

- EXCESS MATERIAL (2) -

EARTHWORK BALANCE

EXCESS MATERIAL (2)

EXCAVATION (BID ITEM)

NOTES:

1121 (EV) -

(1) A DEPTH OF 6" WAS USED FOR QUANTITY PURPOSES.

(2) MATERIAL NOT USED ON PROJECT WILL BECOME THE PROPERTY OF THE CONTRACTOR AND SHALL BE DISPOSED OF OFF THE PROJECT.

COMMON CHANNEL EXCAVATION

1						
						I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED
						BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROBESSIONAL ENGINEER
						UNDER THE LAWS OF THE MATE OF MINNESOTA.
						
		1	İ			SIGNATURE: C. S. C
<u> </u>		1				PRINTED NAME: JAMES E. STUDENSKI
MO	DATE	1	LVD	APPR	DEVICTOR	DATE: 7/23/2012 LIC. NO. 23757
∎ NU	DAIL	BY	UKD	APPR	REVISION	***************************************

DRAWN BY	DATE	S.A.P. 002-634-002
		S.A.P. 002-634-002 TKDA Proj. 14851.000
DESIGN BY		S.P.
CHECKED BY	DATE	S.P.



CITY OF LINO LAKES POND GRADING AND EARTHWORK SUMMARY BIRCH ST (CSAH 34)/WARE RD SIGNALIZATION

SHEET 38 OF 63

***************************************	SAL	VAC	EΑ	ND IN	ISTALL S	SIGN TYP	E "C"	
SIGN NO.		PO:	STS	MTG.	PANEL			
	QUANT.	NO. & LEN.		HT. SIZE		CODE NO.	PANEL LEGEND	
		TYPE	FEET	FEET	INCHES			
C-101	1	1U	10	7	30 x 30	R1-1	STOP	
C-102	1	2U	10	7	54 X 30	R3-30ACA	LANE USE	
C-103	1	2U	10	7	36 X 36	W3-3	SIGNAL AHEAD	

				S	IGN PA	VELS T	/PE "C"	- ROADW	AY]
		POSTS		MTG.	PANEL.					
SIGN NO.	QUANT.	NO.	LEN.	HT. (1)	SIZE	AREA	TOTAL AREA	CODE NO.	PANEL LEGEND	
		TYPE	FT	FEET	INCHES	SQ. FT.	SQ. FT.			
C-01	4	2U	10	7	30 X 36	7.5	30	R4-7	KEEP RIGHT	1 (2
C-02	3	2U	10	7	30 X 30	6.25	18.8	R3-7	RIGHT LANE MUST TURN RIGHT	1
C-03	2	2U	10	7	36 X 36	9	18	W3-3	SIGNAL AHEAD	1
C-04	3	2U	10	7	30 X 30	6.25	18.8	R5-1	DO NOT ENTER	[2
TOTAL							85.6			7

DELIINEATORS AND MARKERS								
ТУРЕ	QUANT.	LOCATION						
X4-2	4	MEDIAN NOSE MOUNTED WITH KEEP RIGHT SIGN	(3)(4)(5)					

PAVI	MENT M	ARKINGS	- EPOXY
	4" SOLID LINE WHITE (LIN FT)	4" SOLID LINE YELLOW (LIN FT)	4" DOUBLE SOLID LINE YELLOW (LIN FT)
OTAL	6,390	1,080	3,125

PAVI	EMENT N	TARKING	S - PREFORN	IED THERM	OPLASTIC
		MENT AGES		0	
	LEFT RIGHT ARROW ARROW (EACH) (EACH)	24" SOLID LINE YELLOW (LIN FT)	24" SOLID LINE WHITE (LIN FT)	CROSS WALK MARKINGS (SQ FT)	
TOTAL	6	11	380	125	756

SPECIFIC NOTES:

- (1) Mounting height is minimum, see sheet 41 for Typical Mounting
- (2) Mounted in concrete, see sheet 42
- (3) See Standard Signs Manual for Hazard markers (X4-2) (background black)
- (4) Install on 3Lb/ft post (MnDOT 3401) (5) Mount 4 (qty) BELOW SIGN C-01

- (a) Post lengths are approximate and include embedment but do not include additional length required for splice.
- (b) See sheet 41 for structural details.
- (c) See Standard Signs Manual for punching code and detailed drawings of type C sign panels.

						Г
		ļ			WARRANGE WITH THE PROPERTY OF	1
		1-				1
	·····					1
			1			1
NO	DATE	BY	CKD	APPR	REVISION	1

I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULLY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

SIGNATURE:

PRINTED NAME: BRYANT J. FICEK

DATE: July 23, 2012 LIC. NO. 42802


S.A.P. 002-634-002 TKDA Proj. 14851.000 S.P.





CITY OF LINO LAKES SIGNING AND STRIPING TABULATIONS


BIRCH ST. (CSAH 34) AND WARE ROAD

SHEET 39 OF 63











GROUND POST MOUNT SIGN INSTALLATION TYPICAL




ISLAND MOUNT BREAK-AWAY SIGN INSTALLATION TYPICAL




2 OF 5


SHEET 42 0F 63

T _Q									2 OF
1.≹2					I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER		S.A.P. 002-634-002		CITY OF LINO LAKES
8/1/201 10:07:22 AME: K:\q					 UNDER THE LAWS OF THE STATE OF MINNESOTA.	DESIGN BY DATE	TKDA Proj. 14851.000	I TKDA	SIGNING & STRIPING DETAILS
ப்ப் வி	1			 	 SIGNATURE: BRYANT & FICEK		S.P.	ENGINEERING - ARCHITECTURE - PLANNING	
DAT	NO DATE	BY C	KD APPR	REVISION	DATE: July 23, 2012 LIC. No. 42802	CHECKED BY DATE	5.r.		BIRCH ST. (CSAH 34) AND WARE ROAD









NOTE:

- ALL DIMENSIONS ARE MINIMUMS
- MAINTAIN 2' CLEAR FROM SIGNS TO BITUMINOUS TRAIL

3 OF 5

32							I HEREB
1 2 1							BY ME O
K:\201							UNDER 7
ME:03							m=a,
s							SIGNATUR
							PRINTED DATE:_J
or.	NO	DATE	BY	CKD	APPR	REVISION	DATE: J
,		***************************************					

I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA SIGNATURE:

PRINTED NAME:

BRYANT J. FICEK


DATE: July 23, 2012 LIC, NO. 42802


S.A.P. 002-634-002
TKDA Proj. 14851.000
SIGN BY _____ DATE _____ S.P.
SECKED BY ____ DATE ____ S.P.



CITY OF LINO LAKES SHEET
SIGNING & STRIPING DETAILS 43
OF
BIRCH ST. (CSAH 34) AND WARE ROAD 63

TYPICAL MESSAGE PLACEMENT FOR TURN LANES





4 OF 5

- 3							
Σ₹.				ľ			I HI BY
24 I			T	Π.			
855							UND
500			1	1			
~으를		***************************************		T			SIGN
680		***************************************	1				PRI!
āĒŒ	NO	DATE	BY	CKD	APPR	REVISION	DAT

ATE: July 23, 2012 LIC, NO. 42802


S.A.P. 002-634-002 TKDA Proj. 14851.000 S.P. S.P.



CITY OF L	NO LAKES	SHEET
SIGNING & STI	RIPING DETAILS	44 0F
		0F
RCH ST. (CSAH 3	4) AND WARE ROA	D 63

BIRCH ST. (CSAH 34) AND WARE ROAD

MARKINGS FOR PEDESTRIAN CROSSWALKS



(L) (W) (S) WIDTH OF WIDTH OF WIDTH OF INSIDE LANE PAINTED AREAS SPACE

- 1.) PAINTED AREAS ARE TO BE CENTERED ON CENTER AND LANE LINES, EVEN IF INTERSECTION IS NOT ALIGNED.
- 2.) LOCATION OF ZEBRA CROSSWALKS AND STOP BARS, SIGNAL LOOPS AND PED RAMPS ARE APPROXIMATE, FINAL LOCATIONS ARE TO BE DETERMINED AND FIELD VERFIED DURING CONSTRUCTION BY THE FIELD ENGR.
- 3.) ZEBRA CROSSWALKS ARE TO BE PARALLEL TO THE DRIVING LANE OR LANES. EVEN IF THE STREET IS ON AN ANGLE TO THE
- 4.) A MIN. OF 1.5' (450mm) CLEAR DISTANCE MUST BE LEFT ADJACENT TO THE CURB. IF LAST PAINTED AREA FALLS INTO THIS AREA, IT MUST BE OMITTED.
- 5.) ON TWO LANE STREETS, USE SPACING SHOWN FOR AN 11' (3.3mm) INSIDE LANE.

NOTES & GUIDELINES

GENERAL INFORMATION:

THE ENGINEER'S INVOLVEMENT IN THE APPLICATION OF THE MATERIAL SHALL BE LIMITED TO FIELD CONSULTATION AND INSPECTION. THE CONTRACTOR WILL PLACE NECESSARY "SPOTTING" AT APPROPRIATE POINTS TO PROVIDE HORIZONTAL CONTROL FOR STRIPING AND TO DETERMINE NECESSARY STARTING AND CUTOFF POINTS, LONGITUDINAL JOINTS. PAVEMENT EDGES AND EXISTING MARKINGS MAY SERVE AS HORIZONTAL CONTROL WHEN SO

EDGE LINES AND LANE LINES ARE TO BE BROKEN ONLY AT INTERSECTIONS WITH PUBLIC ROADS AND AT PRIVATE ENTRANCES IF THEY ARE CONTROLLED BY A YIELD SIGN, STOP SIGN OR TRAFFIC SIGNAL. THE BREAK POINT IS TO BE AT THE START OF THE RADIUS FOR THE INTERSECTION OR AT MARKED STOP LINES OR CROSSWALKS.

A TOLERANCE OF 1/4 INCH UNDER OR 1/4 INCH OVER THE SPECIFIED WIDTH WILL BE ALLOWED FOR STRIPING PROVIDED THE VARIATION IS GRADUAL AND DOES NOT DETRACT FROM THE GENERAL APPEARANCE. BROKEN LINE SEGMENTS MAY VARY UP TO ONE-HALF FOOT FROM THE SPECIFIED LENGTHS PROVIDED THE OVER AND UNDER VARIATIONS ARE REASONABLY COMPENSATORY. ALIGNMENT DEVIATIONS FROM THE CONTROL GUIDE SHALL NOT EXCEED 1 INCH. MATERIAL SHALL NOT BE APPLIED OVER LONGITUDINAL JOINTS. ESTABLISHMENT OF APPLICATION TOLERANCES SHALL NOT RELIEVE THE CONTRACTOR OF THEIR RESPONSIBILITY TO COMPLY AS CLOSELY AS PRACTICABLE WITH THE PLANNED

EPOXY:

THE ROAD SURFACE SHALL BE CLEANED AT THE DIRECTION OF THE ENGINEER JUST PRIOR TO APPLICATION, PAVEMENT CLEANING SHALL CONSIST OF AT LEAST BRUSHING WITH A ROTARY BROOM (NON-METALLIC) OR AS RECOMMENDED BY THE MATERIAL MANUFACTURER AND ACCEPTABLE TO THE ENGINEER, NEW PORTLAND CEMENT CONCRETE SURFACES SHALL BE SANDBLAST CLEANED TO REMOVE ANY SURFACE TREATMENTS AND/OR LAITANCE, ON LOW SPEED (SPEED LIMIT 35 OR LESS) URBAN PORTLAND CEMENT CONCRETE ROADWAYS, SANDBLAST CLEANING SHALL BE USED FOR ALL EPOXY PAVEMENT MARKINGS.

THE EPOXY MARKING APPLICATION SHALL IMMEDIATELY FOLLOW THE PAVEMENT CLEANING. GLASS BEADS SHALL BE APPLIED IMMEDIATELY AFTER APPLICATION OF THE EPOXY RESIN LINE TO PROVIDE AN IMMEDIATE NO-TRACK SYSTEM.

AN EPOXY RESIN LINE 4" WIDE AND 15 MILL THICKNESS (WET), REQUIRES AN APPLICATION RATE OF ONE (1) GALLON OF COMPONENTS FOR 320 FEET OF LINE. GLASS BEADS SHALL BE APPLIED AT A POUND PER GALLON RATE SUFFICIENT TO ACHIEVE AN ACCEPTABLE NO-TRACK SYSTEM.

OPERATIONS SHALL BE CONDUCTED ONLY WHEN THE ROAD PAVEMENT SURFACE TEMPERATURES ARE 50 DEGREES F° OR GREATER.

PERMANENT PAVEMENT MARKINGS SHALL NOT BE PLACED OVER TEMPORARY TAPE MARKINGS.

PAINT:

AT THE TIME OF APPLYING THE MARKING MATERIAL, THE APPLICATION AREA SHALL BE FREE OF CONTAMINATION, THE CONTRACTOR SHALL CLEAN THE ROADWAY SURFACE PRIOR TO THE LINE APPLICATION IN A MANNER AND TO THE EXTENT REQUIRED BY THE ENGINEER.

GLASS BEADS SHALL BE APPLIED IMMEDIATELY AFTER APPLICATION OF THE PAINT LINE.

EXCEPT WHEN USED AS A TEMPORARY MARKING, PAVEMENT MARKINGS SHALL ONLY BE APPLIED IN SEASONABLE WEATHER WHEN AIR TEMPERATURE IS 50°F OR HIGHER AND SHALL NOT BE APPLIED WHEN THE WIND OR OTHER CONDITIONS CAUSE A FILM OF DUST TO BE DEPOSITED ON THE PAVEMENT SURFACE AFTER CLEANING AND BEFORE THE MARKING MATERIAL CAN BE APPLIED.

THE FILLING OF TANKS, POURING OF MATERIALS OR CLEANING OF EQUIPMENT SHALL NOT BE PERFORMED ON UNPROTECTED PAVEMENT SURFACES UNLESS ADEQUATE PROVISIONS ARE MADE TO PREVENT SPILLAGE OF MATERIAL.

5 OF 5

REVISION

BRYANT J. FICEK PRINTED NAME:_ DATE: July 23, 2012 LIC. NO. 42802

S.A.P. 002-634-002 TKDA Proj. 14851.000 DESIGN BY S.P. S.P. HECKED BY_



CITY OF LINO LAKES SIGNING & STRIPING DETAILS

BIRCH ST. (CSAH 34) AND WARE ROAD

45 0F 63

SHEET

ABBREVIATIONS

ACCESSIBLE PEDESTRIAN SIGNAL ADVANCE WARNING FLASHER COUNT DOWN D2-1 (e.g.) DEG DWK EO.G EVP F&I DETECTOR (PHASE 2, NO. 1) DEGREES DON'T WALK EQUIPMENT GROUND EMERGENCY VEHICLE PRE-EMPTION FURNISH AND INSTALL FL FYA FYLA GLA GRN FLASH/FLASHING FLASHING YELLOW ARROW FLASHING YELLOW LEFT ARROW GREEN LEFT ARROW GR. RD.
GRA
GTA
HH
HPS
IND
IMC
INP
INS. GR.
JB
LED
LUM
NEU GREEN RIGHT ARROW GREEN THRU ARROW HANDHOLE HIGH PRESSURE SODIUM INDICATION INTERMEDIATE METAL CONDUIT INSULATED GROUND JUNCTION BOX LIGHT EMITTING DIODE LUMINAIRE NEUTRAL NONMETALLIC CONDUIT
PEDESTRIAN INDICATION (PHASE 1, NO. 1) P1-1 (e.g.) PEDESTRIAN INDICATION (PHASE PB PUSH BUTTON PB2-1 (e.g.) PUSH BUTTON (PHASE 2, NO. 1) PEC PHOTOELECTRIC CELL PED PEDESTRIAN PVC POLYVINYL CHLORIDE (CONDUIT) RED RED INDICATION R&S REMOVE AND SALVAGE RLA RED LEFT ARROW RSC RIGID STEEL CONDUIT S&I SALVAGE AND INSTALL SOP SOURCE OF POWER SPR SPARE STA STATION WLK WALK YEL YELLOW INDICATION YLA YELLOW RIGHT ARROW

SYMBOLS

EQ.G CONNECTION

EVP CONFIRMATORY LIGHT

EVP DETECTOR

EVP DETECTOR AND CONFIRMATORY LIGHT

FIBER OPTIC VAULT

LUMINAIRE NO.

SIGNAL BASE NO.

SIGNAL FACE NO./FLASHER FACE NO.

BARREL MOUNT BASE NO.

WOOD POLE NO.


SPLICE

VIDEO DETECTION

MICROWAVE DETECTION

SONIC DETECTION

FOR PLANS AND UTILITIES SYMBOLS SEE TECHNICAL MANUAL



THE FOLLOWING STANDARD PLATES, APPROVED BY THE FEDERAL HIGHWAY ADMINISTRATION, SHALL APPLY ON THIS PROJECT

TRAFFIC SIGNAL STANDARD PLATES

PLATE NO.	DESCRIPTION
8110E	TRAFFIC SIGNAL BRACKETING (POLE MOUNTED)
8111E	TRAFFIC SIGNAL BRACKETING (PEDESTAL MOUNTED) (3 SHEETS)
8112G	PEDESTAL FOUNDATION (TRAFFIC CONTROL SIGNALS)
8114A	P.V.C. HAND HOLE/PULL BOX (NO VEHICLE LOAD)(2 SHEETS)
8119C	GRAND MOUNTED CABINET FOUNDATION
8120P	POLE FOUNDATION (PA85)
8121G	TRANSFORMER BASE & POLE BASE PLATE (PA85, PA90, & PA100)(2 SHEETS)
8122F	PEDESTAL & PEDESTAL BASE (FOR TRAFFIC CONTROL SIGNALS SUPPORT)(2 SHEETS)
8123G	POLE & MAST ARM - LUMINAIRES & TRAFFIC LIGHT ASSEMBLY (FOR ALL POLE TYPES)(2 SHEETS)
8126J	POLE FOUNDATION (PA90 & PA100)
8132B	PREFORMED RIGID PVC CONDUIT LOOP DETECTOR (3 SHEETS)

NO DATE BY CKD APPR REVISION

I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTAL SIGNATURE:

PRINTED NAME: BRYANT J. FICEK


DATE: July 23, 2012 LIC, NO. 42802


DRAWN BY ____ DATE ____ S.A.P. 002-634-002
TKDA Proj. 14851.000
S.P.
CHECKED BY ____ DATE ____ S.P.



CITY OF LINO LAKES
SIGNAL PLAN AND DETAILS
STANDARD PLATES AND DETAILS
BIRCH ST. (CSAH 34) AND WARE ROAD


SHEET 46 OF 63





(**) = SPACING BETWEEN STIFFENERS SHALL NOT EXCEED 36 INCHES AND SHALL BE UNIFORMLY SPACED. SEE SPECIAL PROVISIONS AND STANDARD SIGN MANUAL, PAGE 105A (REVISION DATE 7-06-07) FOR BRACKET SPACING REQUIREMENTS.

SIGNS FOR TRAFFIC SIGNAL SYSTEM										
			SIGN	- PANELS	TYPE C (I	FURNISH	I AND INS	TALL)		
SIGN PANEL	SIZE (IN.)	NO. REQ.	NO. POSTS / STIFFENERS PER SIGN	BAND SPACING (**)	SQ. FT. PER SIGN	TOTAL AREA (SQ., FT.)	POLE NO.	a	b	PANEL LEGEND
R10-12	30X36	2	(1)	*	7.50	15.00	2,4	2'	***	LEFT TURN YIELD ON GREEN




D-1; 3.0" Radius, 1.0" Border, White on Green;

[Birch Street] E Mod;

NOTES:

- 1) COLOR FOR ALL NEW TYPE D SIGNS SHALL BE WITH LEGEND AND BORDER ON GREEN BACKGROUND, FULLY REFLECTORIZED
- 2) CORNERS EXTENDING BEYOND THE BORDER SHALL NOT BE TRIMMED.
- 3) FOR STRUCTURAL DETAILS OF MAST ARM MOUNTED SIGNS, SEE STANDARD SIGNS MANUAL, PAGE 105A (REVISED DATE 7/06/07) AND SPECIAL PROVISIONS.
- 4) SEE STANDARD SIGNS MANUAL FOR DETAILED DRAWING OF TYPE C SIGN PANELS
- 5) FURNISHING AND INSTALLING TYPE C AND D SIGNS SHALL BE CONSIDERED INCIDENTAL TO ITEM NO. 2565 (TRAFFIC CONTROL SIGNAL SYSTEM). SEE SPECIAL PROVISIONS.
- 6) ALL NEW TYPE C AND D SIGN PANELS SHALL BE FABRICATED USING HP SHEETING. SEE SPECIAL PROVISIONS

- F	T		1	T			I
y ₹ }			1				BY
18 °							 ٩IJ
~ E===				ļ			 SI
3.52	<u> </u>		<u> </u>				 -
				<u>L</u> .	<u> </u>		PR
u.	NO	DATE	BY	CKD	APPR	REVISION	DA



DRAWN BY DATE	S.A.P. 002-634-002 TKDA Proj. 14851.000
	S.P.
CHECKED BY DAYE	S.P.




CITY OF LINO LAKES

SIGNAL PLAN AND DETAILS
SIGNAL SIGNING DETAILS
BIRCH ST. (CSAH 34) AND WARE ROAD

SHEET 47 OF 63

TYPICAL PAD WITH CONTROLLER CABINET AND SERVICE CABINET

SEE INTERSECTION LAYOUT FOR CABLE INFORMATION (NOT TO SCALE)




NOTES:

- 1. THE ANCHOR RODS, NUTS AND WASHERS FOR EACH COUNTY FURNISHED CONTROLLER AND CABINET SHALL BE FURNISHED BY THE COUNTY AND INSTALLED BY THE CONTRACTOR.
- 2. THE UPPER PART OF EACH EQUIPMENT PAD SHALL BE BEVELLED OR CHAMFERED IN A NEAT MANNER AS DIRECTED
- 3. THE TOP OF THE CONDUITS SHALL BE THREADED AND CAPPED AFTER INSTALLATION (UNTIL CABLES ARE INSTALLED).
- 4. CONDUIT SHALL PROJECT A MINIMUM OF 2" ABOVE THE CONCRETE AND SHALL BE LOCATED INSIDE THE CABINET WHERE DIRECTED BY THE ENGINEER, BUT SHALL NOT INTERFERE WITH THE CABINET FUNCTIONS (SUPPORTING
- 5. CONCRETE MIX 3A32 OR EQUAL SHALL BE USED FOR THE EQUIPMENT PAD AND SIDEWALK.
- 6. CONDUITS WITH BOTH ENDS TERMINATING WITHIN THE PAD SHALL NOT BE INSTALLED BELOW THE CONCRETE.
- 7. THE EXACT LOCATIONS OF CONDUITS WITHIN EACH PAD SHALL BE DETERMINED BY THE ENGINEER IN THE FIELD.
- 8. ANCHOR RODS SHALL PROJECT A MINIMUM OF 3" ABOVE THE CONCRETE, BUT SHALL NOT INTERFERE WITH THE CABINET FUNCTIONS (SUPPORTING MEMBERS, ETC.).
- CONTRACTOR SHALL PROVIDE MINIMUM 4 INCH CLEARANCE BETWEEN CONTROLLER AND SERVICE CABINETS ON THE EQUIPMENT PAD FOUNDATIIONS AS SHOWN.
- 10. CABINETS TO BE CENTERED (LEFT & RIGHT) ON THE PAD.
- 11. BRUSH ON ANTI-SEIZE LUBRICANT MUST BE APPLIED TO ALL ANCHOR ROD THREADS PROTRUDING ABOVE THE CONCRETE PAD BEFORE THE CABINET IS SET.


REVISION

CKD APPR






FRONT VIEW



CONTROLLER CABINET TYPE "P" & "R" **BOLT PATTERN**




BRYANT JL FICEK

PRINTED NAME:__


ECKED BY DATE: July 23, 2012 LIC. NO. 42802

S.A.P. 002-634-002 TKDA Proj. 14851.000 S.P. S P


CITY OF LINO LAKES SHEET 48 0F SIGNAL PLAN AND DETAILS EQUIPMENT PAD DETAILS 63 BIRCH ST. (CSAH 34) AND WARE ROAD




REVISION




BOLT ON HUB & FLANGE



TOP VIEW



- 1. ALL THREADED SURFACES TO BE COATED WITH ANTI-SEIZE COMPOUND.
- 2. USE SIGNAL HEAD MOUNTED SPACERS FOR 4 & 5 SECTION POLY HEADS.
- BLIND THREADED INSERTS (RIVET NUT) MUST BE INSERTED USING MANUFACTURERS SPECIFIC INSTALLATION TOOL. NO OTHER METHOD OF INSTALLATION IS ACCEPTABLE.
- 4. SEE STANDARD PLATE NUMBER 8122 FOR ADDITIONAL PEDESTAL POLE DETAILS.



TYPICAL PEDESTAL MOUNTING NOT TO SCALE

CITY OF LINO LAKES SIGNAL PLAN AND DETAILS POLE MOUNT DETAILS

BIRCH ST. (CSAH 34) AND WARE ROAD

SHEET 49 0F 63

HOLES (2) FOR BLIND THREADED INSERT DRILL 3/4" HOLE

FOR WIRE

HECKED BY DATE: July 23, 2012 LIC. NO. 42802

S.P.

ENGINEERING * ARCHITECTURE * PLANNING

